

FORM
5Rev
09/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400864700

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 100322

Contact Name: EILEEN ROBERTS

Name of Operator: NOBLE ENERGY INC

Phone: (303) 228-4330

Address: 1625 BROADWAY STE 2200

Fax: (303) 228-4286

City: DENVER State: CO Zip: 80202

API Number 05-123-39878-00

County: WELD

Well Name: Tripucka State

Well Number: LD02-74-1AHN

Location: QtrQtr: SWSE Section: 2 Township: 9N Range: 58W Meridian: 6

Footage at surface: Distance: 615 feet Direction: FSL Distance: 1953 feet Direction: FEL

As Drilled Latitude: 40.775020 As Drilled Longitude: -103.828730

GPS Data:

Date of Measurement: 11/26/2014 PDOP Reading: 2.3 GPS Instrument Operator's Name: Toa Sagapolutele

** If directional footage at Top of Prod. Zone Dist.: 1268 feet. Direction: FSL Dist.: 1759 feet. Direction: FEL

Sec: 2 Twp: 9N Rng: 58W

** If directional footage at Bottom Hole Dist.: 330 feet. Direction: FNL Dist.: 1760 feet. Direction: FEL

Sec: 2 Twp: 9N Rng: 58W

Field Name: WILDCAT

Field Number: 99999

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 01/01/2015 Date TD: 01/06/2015 Date Casing Set or D&A: 01/07/2015

Rig Release Date: 01/07/2015 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 9579 TVD** 5579 Plug Back Total Depth MD 9567 TVD** 5579

Elevations GR 4675 KB 4705 Digital Copies of ALL Logs must be Attached per Rule 308A ☒

List Electric Logs Run:

CBL/Mud/Gamma. The designated resistivity log on this pad will be, Tripucka State LD 02-74-1AHN

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42.09	30	130	80	0	130	VISU
SURF	13+1/2	9+5/8	36	30	1,241	509	0	1,241	VISU
1ST	8+3/4	7	26	30	5,915	430	1,555	5,915	CBL
1ST LINER	6+1/8	4+1/2	11.6	5799	9,569				

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PIERRE	2,330				
PARKMAN	3,213				
SUSSEX	3,820				
SHANNON	4,206				
NIOBRARA	5,597				

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: EILEEN ROBERTS

Title: REGULATORY ANALYST Date: _____ Email: eileen.roberts@nblenergy.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
400864791	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400875562	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
400864773	PDF-RESISTIVITY	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400864777	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400864781	PDF-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400864783	PDF-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400864785	LAS-GAMMA RAY	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400864787	PDF-GAMMA RAY	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400864789	PDF-GAMMA RAY	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400864798	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)