

**FORM**  
**5**  
Rev  
09/14

**State of Colorado**  
**Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:  
400849838

Date Received:

**DRILLING COMPLETION REPORT**

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type  Final completion  Preliminary completion

OGCC Operator Number: 47120 Contact Name: Kayla Hesseltine  
 Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6552  
 Address: P O BOX 173779 Fax: \_\_\_\_\_  
 City: DENVER State: CO Zip: 80217-

API Number 05-123-40834-00 County: WELD  
 Well Name: GREEN Well Number: 2C-8HZ  
 Location: QtrQtr: NWNW Section: 8 Township: 1N Range: 65W Meridian: 6  
 Footage at surface: Distance: 356 feet Direction: FNL Distance: 1018 feet Direction: FWL  
 As Drilled Latitude: 40.072313 As Drilled Longitude: -104.693644

GPS Data:  
 Date of Measurement: 02/06/2015 PDOP Reading: 2.0 GPS Instrument Operator's Name: Carli Sloan

\*\* If directional footage at Top of Prod. Zone Dist.: 296 feet. Direction: FSL Dist.: 1932 feet. Direction: FWL  
 Sec: 5 Twp: 1N Rng: 65W  
 \*\* If directional footage at Bottom Hole Dist.: 27 feet. Direction: FSL Dist.: 1995 feet. Direction: FWL  
 Sec: 8 Twp: 1N Rng: 65W

Field Name: WATTENBERG Field Number: 90750  
 Federal, Indian or State Lease Number: \_\_\_\_\_

Spud Date: (when the 1st bit hit the dirt) 01/25/2015 Date TD: 05/05/2015 Date Casing Set or D&A: 05/06/2015  
 Rig Release Date: 06/04/2015 Per Rule 308A.b.

Well Classification:  
 Dry  Oil  Gas/Coalbed  Disposal  Stratigraphic  Enhanced Recovery  Storage  Observation

Total Depth MD 13581 TVD\*\* 7345 Plug Back Total Depth MD 13478 TVD\*\* 7345

Elevations GR 4971 KB 4987 **Digital Copies of ALL Logs must be Attached per Rule 308A**

List Electric Logs Run:  
CBL, GR

**CASING, LINER AND CEMENT**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42.1	0	80	64	0	80	VISU
SURF	13+1/2	9+5/8	36	0	1,561	591	0	1,561	VISU
1ST	7+7/8	5+1/2	17	0	13,572	1,300	970	13,572	CBL

### STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

### FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	4,575				
SHARON SPRINGS	7,332				
NIOBRARA	7,367				
FORT HAYS	7,809				
CODELL	8,488				
CARLILE	11,088				

Comment:

Due to anti-collision needs and the variability of directional drilling, our as-drilled BHL could be different than the permitted. This well is a conventional horizontal (monobore).

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Kayla Hesseltine

Title: Regulatory Specialist

Date: \_\_\_\_\_

Email: kayla.hesseltine@anadarko.com

### Attachment Check List

Att Doc Num	Document Name	attached ?	
<b>Attachment Checklist</b>			
400869357	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400849850	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<b>Other Attachments</b>			
400849845	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400849848	LAS-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400849849	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400878101	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)