

Anadarko Daily Summary Report

Well: FT ST VRAIN 19

Project:COLORADO-WELD-NAD83-UTM13

Site:FT ST VRAIN 19

Rig name no.:CONCORD 5/5

Event: ABANDONMENT

Start date: 6/22/2015

End date:

Spud date: 2/5/1993

Active datum: RKB @4,791.99usft (above Mean Sea Level)

UWI: 0/3/N/67/W/9/O/SWNW/6/0/0/0/0/0/0/0

Report no.	Report date	MD (usft)	24 hr summary
1	05/29/2015		MIRU, SUMMIT SLICKLINE, RIH TAG FILL @ 7108, RAN PRESSURE BOMB TO 7048.
2	06/22/2015		MIRU Concord #5 RU pump & tank TP:600, CP:500, SP:0. Blew down well(csg blew down instantly) controlled tbg w/30 bbl ND 5K WH NU 5K BOP, RU work floor released Pkr TOO H tally out 224 jts RU Warrior WL set 4.5 CIBP @ 6810' RDWL RU Hole Seekers SEE REMARKS
3	06/23/2015		No pressure on well, broke circulation, RU Sanjel pumped 25 sks of thermal 35 cmt 15.8 ppg, 1.51 cf/sk 6.7 bbls of cmt 2bbl/min @500psi RD Sanjel TOO H SB 3756' of tbg RU Warrior WL shot SQ holes @ 4260' & 3700' RDWL, TIH Thunderbird's 4.5 CICR SEE REMARKS
4	06/24/2015		No pressure on well, unlanded csg NU spool & 5K BOP RU work floor TOO H LD 19 jts 4.5 csg on trailer, X/O tools TIH 2 3/8 tbg to 860' 27 jts circulated well RU Sanjel pumped 10 bbls SAPP & 210 sks type 3 cmt 14.8 ppg, 1.34 cf/sk RD Sanjel TOO H SEE COMMENTS
5	07/22/2015		DUG UP SURFACE CASING. CUT CASING 6' BELOW GL. TAGGED @ 73'. FILLED CASING STUB WITH 41 BAGS 5000 PSI CEMENT. CAPPED CASING WITH A METAL PLATE CONTAINING WELL INFO. BACKFILLED.

REMARKS:

06/22/15 - tester TIH test tbg in 3000 psi 217 jts tag CIBP PUH 5' RD tester circulated gas out PT CIBP to 1000/psi 15/ mins held good. SWI SDFN

06/23/15 - set it @ 3756' established circulation of 2 bbl/min @ 1200 psi, for 15 mins RU Sanjel pumped 20 bbls of SMS & 310 sks class G cmt 15.8 ppg, 1.15 cf/sk 63.5 bbls of cmt @ 2 bbl/min @ 1000 psi. displaced 3 bbls of cmt on top of CICR RD Sanjel.(Had good circulation throughout the job, got some gas & drilling mud on returns) TOO H SB 860' 26 jts LD rest of tbg in trailer. RU Warrior WL RIH jet cut csg @ 760' RDWL circulated gas out 2.5 bbl/min @ 500 psi for 45 minutes, got some gas & drilling mud on returns. ND BOP & WH SWI SDFN

06/24/15 - to 120' circulated well clean, TOO H LD all tbg WOC 4 hrs, TIH tagged TOC @ 190' w/6 jts LD tbg ND BOP & spool RU Warrior WL RIH set 8 5/8 CIBP @ 80' RDWL NU WH PT CIBP to 1000psi/15mins held good RDMO Concord #5 SDFN