

Not to Scale

8 5/8"
Surf Csg @ 272'
TOC: Surf

Perf @ 740'

Squeezed w/ 295 sx cmt

TOC: TOC Unknown

SN

Top Perf: 2790'

Bot Perf : 2828'

4.5" Csg set @: 2923'

TD 2926'

PBTD: 2882'

Wellbore Dia			Price #1-12		
Status	Producing		Operator	Stelbar Oil Corp	
Lease	Price		Zone	Niobrara	
Field	DeNova		API	05-121-09802-00	
State:	Colorado		Division:		
Location	1370' FSL & 1230' FEL, NE/4 SE/4 Sec 12-T2S-R49W, 6th PM, Washington County, CO: ? Acre Spacing				
Reference:					
KB	4,339	TVD	2926'	Orig PBTD	2882'
GL	4,332	MTD	2926'	SN	2757'
Casing	Weight/Grade	Depth	Cmt Sx	Hole	TOC
N/A Conductor					
8 5/8"	24#/K-55	272'	200	12 1/4"	Circ
4.5"	10.5#,K-55	2923'	150 sx 50/50 Poz	7 7/8"	TOC Unknown
Spud	5/24/1982		Top Perf	2790'	
Completion	7/1/1982		Bot Perf	2828'	
Perf: 2790'-2797'; 2800'-2804'; 2808'-2828', 31' @ 2 SPF, 62 holes. Stim w/ 500 bbls versagel1300, 50,000# 20/40 sand, 40,000# 10/20 sand, 65 tons CO2 job					
Date sketch checked		6/10/15	by:	TWL	
Date tubulars checked		6/10/15	by:	TWL	
Current Tubulars					
Tubing String				Length, ft	Depth, ft
Size	Grade	# Jnts	Type		
			KBE	7.00	7.00
2 3/8	J-55	87	Plain Tbg	2789.22	2796.22
2 3/8		1	SN	1.10	2797.32
					2797.32
					2797.32
					2797.32
Bottom of Tbg String:					2797.32
Rods String				Length, ft	Depth, ft
Size	Grade	# Rods			
Latitude and Longitude Location:					
Latitude:				39.892047	
Longitude:				-102.806064	