

MARALEX RESOURCES, INC.

Current Wellbore

WELL NAME	South Shale Ridge 3-20
LOCATION	NENW Section 20 T8S R98W 6PM
GPS	39.350469 -108.353371 PDOP 3.7
API #	05-077-08612

FIELD	South Shale Ridge
COUNTY	Mesa
GPS OPERATOR	M. Nastal
FORMATION	Cameo Coal

CASING

SURFACE

SIZE & WT	8 ⁵ / ₈ " 24#
SET @	239'
HOLE SIZE	12 ¹ / ₄ "
CEMENT	220 sxs
Thixotropic w/ 2% CaCl	
TOC @ surface	

8⁵/₈" @ 239'

PRODUCTION

SIZE & WT	4 ¹ / ₂ " 11.6#
SET @	4089'
HOLE SIZE	7 ⁷ / ₈ "
CEMENT	600 sxs Highbond 50
w/ 2% CaCl	
TOC @ 1500'	

STAGE TOOL

@ NA

PERFORATIONS

Top	3693'
Bottom	3953'
28 holes	

FORMATION TOPS

Wasatch	surface
Mesa Verde	1502'
Cameo Coals	3674'
Rollins	3955'

Perforations 3693'-3953'
Top of 2³/₈" tubing fish
at 3713'

PBTD 4073'

4¹/₂" @ 4089'

TOTAL DEPTH 4105'