



DRILLING COMPANY, INC.

WICHITA, KANSAS

Current Wellbore Configuration

Date:	8/13/2015
Well Name:	State-Hines #1-16
Location:	SE SE 16-T13S-R47W
County:	Cheyenne
State:	Colorado
API:	05-017-06568
KB:	4380'
GL:	4369'
Spud Date:	9/26/1985

8-5/8", 24# set at 350'
Cmt to surf w/225 sx.

Top of Cement at 4216' (CBL dated 10/12/85)

Marmaton Perforations at 4875'-4894' (42 holes)

CIBP set at 4930'

Morrow Sand Perfs at 5414'-5417' (10 holes)

5-1/2", 17# csg set at 5558'

Cemnted with 175 sks. 50/50 Pozmix