

**APPLICATION FOR PERMIT TO:**

**Drill**       Deepen       Re-enter       Recomplete and Operate

TYPE OF WELL    OIL     GAS     COALBED     OTHER \_\_\_\_\_      Refilling

ZONE TYPE      SINGLE ZONE     MULTIPLE ZONES     COMMINGLE ZONES       Sidetrack

Date Received:  
08/06/2015

Well Name: Taoka KF      Well Number: 01-032HN

Name of Operator: GREAT WESTERN OPERATING COMPANY LLC      COGCC Operator Number: 10110

Address: 1801 BROADWAY #500

City: DENVER      State: CO      Zip: 80202

Contact Name: Callie Fiddes      Phone: (303)398-0550      Fax: ( )

Email: regulatorypermitting@gwogco.com

**RECLAMATION FINANCIAL ASSURANCE**

Plugging and Abandonment Bond Surety ID: 20090080

**WELL LOCATION INFORMATION**

QtrQtr: SESE      Sec: 1      Twp: 1N      Rng: 65W      Meridian: 6

Latitude: 40.073839      Longitude: -104.605981

Footage at Surface: 224 feet      FNL/FSL      FSL      928 feet      FEL/FWL      FEL

Field Name: WATTENBERG      Field Number: 90750

Ground Elevation: 4957      County: WELD

GPS Data:  
Date of Measurement: 11/30/2012    PDOP Reading: 1.8    Instrument Operator's Name: R. Kay

If well is  Directional       Horizontal (highly deviated)      **submit deviated drilling plan.**

Footage at Top of Prod Zone:    FNL/FSL      FEL/FWL      Bottom Hole:    FNL/FSL      FEL/FWL

460    FSL      2330    FEL      470    FNL      2318    FEL

Sec: 1    Twp: 1N    Rng: 65W      Sec: 1    Twp: 1N    Rng: 65W

**LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT**

Surface Ownership:  Fee       State       Federal       Indian

The Surface Owner is:       is the mineral owner beneath the location.  
(check all that apply)       is committed to an Oil and Gas Lease.  
    has signed the Oil and Gas Lease.  
    is the applicant.

The Mineral Owner beneath this Oil and Gas Location is:  Fee       State       Federal       Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: \_\_\_\_\_      Surface Surety ID: \_\_\_\_\_

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

S/2 Sec 1, NW Sec 1

Total Acres in Described Lease: 480 Described Mineral Lease is:  Fee  State  Federal  Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 1304 Feet  
Building Unit: 1052 Feet  
High Occupancy Building Unit: 5280 Feet  
Designated Outside Activity Area: 5280 Feet  
Public Road: 212 Feet  
Above Ground Utility: 264 Feet  
Railroad: 5280 Feet  
Property Line: 224 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a:  Buffer Zone  
 Exception Zone  
 Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 606 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 460 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

W2E2, E2W2 Sec 1

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		320	GWA

## DRILLING PROGRAM

Proposed Total Measured Depth: 11831 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 307 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling?     No      
 Will salt based (>15,000 ppm Cl) drilling fluids be used?     No      
 Will oil based drilling fluids be used?     Yes      
 BOP Equipment Type:  Annular Preventor     Double Ram     Rotating Head     None

**GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING**

Water well sampling required per Rule     318A    

**DRILLING WASTE MANAGEMENT PROGRAM**

Drilling Fluids Disposal:     OFFSITE          Drilling Fluids Disposal Methods:     Commercial Disposal    

Cuttings Disposal:     OFFSITE          Cuttings Disposal Method:     Commercial Disposal    

Other Disposal Description:

Beneficial reuse or land application plan submitted?     No    

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

**CASING PROGRAM**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	42	0	80	121	80	0
SURF	13+1/2	9+5/8	36	0	2000	832	2000	0
1ST	7+7/8	5+1/2	17	0	11831	1081	11831	0

Conductor Casing is NOT planned

**DESIGNATED SETBACK LOCATION EXCEPTIONS**

Check all that apply:

- Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

**GREATER WATTENBERG AREA LOCATION EXCEPTIONS**

Check all that apply:

- Rule 318A.a. Exception Location (GWA Windows).
- Rule 318A.c. Exception Location (GWA Twinning).

**RULE 502.b VARIANCE REQUEST**

Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

**OTHER LOCATION EXCEPTIONS**

Check all that apply:

- Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: \_\_\_\_\_

Is this application being submitted with an Oil and Gas Location Assessment application? \_\_\_\_\_ Yes \_\_\_\_\_

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Callie Fiddes \_\_\_\_\_

Title: Regulatory Specialist Date: 8/6/2015 Email: regulatorypermitting@gwogco.c

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Expiration Date: \_\_\_\_\_

API NUMBER

05

### Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

## Best Management Practices

No	BMP/COA Type	Description
1	Planning	One of the first wells drilled on the pad will be logged with open-hole Resistivity and Gamma Ray Log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing id production liner is run) into the surface casing. The horizontal portion of every well will be logging with a measure-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open hole logs shall clearly state "No open-hole logs were run" and shall clearly identify (by API#, well name and number) the well in which open-hole logs were run.
2	General Housekeeping	General housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with storm water runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup will consist of patrolling the roadways, access areas, and other work areas to pick up trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly and promptly.
3	Drilling/Completion Operations	Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed well path with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottom hole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.
4	Drilling/Completion Operations	Great Western will comply with the "COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area", dated May 29, 2012

Total: 4 comment(s)

### Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

### Attachment Check List

Att Doc Num	Name
400875777	FORM 2 SUBMITTED
400875844	DIRECTIONAL DATA
400875845	DEVIATED DRILLING PLAN
400875846	WELL LOCATION PLAT
400875854	SURFACE AGRMT/SURETY
400877888	EXCEPTION LOC REQUEST
400880055	OffsetWellEvaluations Data
400880590	PROPOSED SPACING UNIT
400884617	EXCEPTION LOC WAIVERS

Total Attach: 9 Files

## General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Returned to draft. 1.) Related Forms tab is missing the information for the submitted Form 2A. 2.) Please clarify the Lease information. 3.) Exception Location Waiver attachment is missing-Cannot find the waiver within the provided SUA. Safety setback for an Above Ground Utility is 200' per Rule 603.a.(1)- a comment is required to explain why this well is located within a designated setback.	8/11/2015 7:15:05 AM

Total: 1 comment(s)

