

US ROCKIES REGION			
Anadarko Daily Summary Report			
Well: FT ST VRAIN 26			
Project:COLORADO-WELD-NAD83-UTM13		Site:FT ST VRAIN 26	Rig name no.:LEED ENERGY/721
Event: ABANDONMENT		Start date: 8/6/2015	End date: Spud date: 3/24/1993
Active datum: RKB @4,765.99usft (above Mean Sea Level)		UWI: 0/3/N/67/W/3/0/SWNW/6/0/0/0/0/0/0/0	
Report no.	Report date	MD (usft)	24 hr summary
1	08/06/2015		MIRU LEED 721, KILL WELL TP-600#, CP-600#, SP-0#, ND WH, NU BOP, UNLAND TBG W/28,000LBS, TOO, RIH W/3.75" GUAGE RING TO 6780', RIH W/CIBP SET @ 6740', SDFN
2	08/07/2015		TIH TO 6738' W/213JTS 2.375"TBG HYDROTEST TO 3000#, CIRCULATE GAS OUT FULL RETURNS, PT CIBP TO 1000# FOR 15MIN, GOOD TEST, PUMP 25SX CMT PLUG FROM 6738' TO 6305', PUH TO 6059', CIRCULATE CLEAN, TOO, SDFN
3	08/10/2015		RIH SHOOT SQZ HOLES @ 4210' & 3810', TIH SET CIBP @ 3848' W/122JTS 2.375"TBG, CIRCULATE FULL RETURNS, PUMP 180SX CMT SQZ, PUH TO 3021', CIRCULATE CLEAN, TOO, RIH CUT CSG @ 820', ND BOP, ND WH, UNLAND CSG W/10,000LBS, NU BOP, CHECK COMMENTS
4	08/11/2015		TIH TAG TOC W/5JTS 2.375"TBG @ 140', TOO, ND BOP, ND WH, RIH SET CIBP @ 80', NU WH & PT CIBP TO 1000# FOR 15MIN GOOD TEST, RDMO LEED 721 TO WEBB 32-2J5
5	08/21/2015		DUG UP SURFACE CASING. CUT CASING 6' BELOW GL. TAGGED @ 71'. FILLED CASING STUB WITH 36 BAGS 5000 PSI CEMENT. CAPPED CASING WITH A METAL PLATE CONTAINING WELL INFO. BACKFILLED.

COMMENTS:

08/10/15 - TOO LD CSG, TIH W/29JTS 2.375"TBG + 1X8'SUB TO 921', CIRCULATE FULL RETURNS, PUMP 220SX CMT PLUG FROM 100' TO 921', PUH TO 100', CIRCULATE CLEAN, TOO, SDFN