

US ROCKIES REGION

Anadarko Daily Summary Report

Well: PEAKS 33-2

Project:COLORADO-WELD-NAD83-UTM13

Site:PEAKS 19-2

Rig name no.:BASIC 1524/1524

Event: WELL WORK EXPENSE

Start date: 8/10/2015

End date:

Spud date: 2/17/2011

Active datum: RKB @5,047.00usft (above Mean Sea Level)

UWI: CW/SW/0/1/N/68/W/2/0/0/6/PM/S/1293/W/0/1601/0/0

Report no.	Report date	MD (usft)	24 hr summary
1	08/10/2015		MIRU SUMMIT SLICKLINE TAG@8504'KB.MIRU BASIC 1524. CONTROL WELL, W/50BBL'S NU BOP'S, FUNCTION TEST, MIRU EMI (PRS) TOO H EMI TBG W/ 268 GOO JNTS, LD 1 BAD2.375 TBG. SWI SDFN.
2	08/11/2015		CONTROL WELL. TIH RBP SET@6411'. CIRCULATE GAS OUT. PSI TEST 4.5" CSG TO 1000# FOR 15MIN, GOOD TEST, SPOT SAND. TOO H, MIRU WARRIOR WL RUN LOG 3010# TO SURFACE. TO VERIFY CEMENT@2821' . ND UNLAND CSG, NU SWI SDFN
3	08/12/2015		TIH W/ 53JNT'S 1.25 TBG EOT@ 1732'. CIRCULATE ANNULUS CONDITION HOLE. LD 5 JNTS 48JNT'S IN HOLE, EOT @1567'.SWI. SDFN.
4	08/13/2015		TIH 5 JNT'S EOT@1732',CIRCULATE CONDITION HOLE. SPOT 20BBL'S, LD 7JNT'S EOT@1503'. MIRU SANJEL CEMENTERS. PUMP SPACER'S, & 170SX (41.3BBL'S) TYPE III CEMENT , DISPLACE, TOO H 1.25 TBG.ND, RELAND CSG@75K,NU BOP'S SWI, SDFN.
5	08/14/2015		MIRU WAARIOR RUN CBL 1704'-15' W/TOC@596'-BOC@1520' . TIH CO SAND RETRIEVE RBP@6411' W/204JNT'S. TOO H. PU BAILER TIH TAG FILL@8504'. BAIL FILL TO 8543' w/ 272 JNT'S. TOO H LD BAILER, SWI,SDFN
6	08/17/2015		TIH LAND TBG 8433' KB W/268JNT'S 2.375 TBG. BRAOCH TO ABOVE XN NIPPLE. MIRU HYDEROTESTER TORQUE & PSI TEST WH TO 5000# FOR 15MIN, GOOD TEST, RDMO BASIC 1524.