

Weld County, Colorado, Northern Part

74—Vona sandy loam, 3 to 9 percent slopes

Map Unit Setting

National map unit symbol: 3610

Elevation: 4,000 to 5,500 feet

Mean annual precipitation: 13 to 15 inches

Mean annual air temperature: 48 to 55 degrees F

Frost-free period: 130 to 160 days

Farmland classification: Not prime farmland

Map Unit Composition

Vona and similar soils: 85 percent

Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Vona

Setting

Landform: Plains

Down-slope shape: Linear

Across-slope shape: Linear

Parent material: Calcareous sandy alluvium and/or eolian deposits

Typical profile

H1 - 0 to 6 inches: sandy loam

H2 - 6 to 15 inches: sandy loam, fine sandy loam

H2 - 6 to 15 inches: loamy sand

H3 - 15 to 60 inches:

Properties and qualities

Slope: 3 to 9 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Well drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): High (1.98 to 6.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum in profile: 15 percent

Salinity, maximum in profile: Nonsaline to slightly saline (0.0 to 4.0 mmhos/cm)

Available water storage in profile: Moderate (about 7.6 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 6e

Hydrologic Soil Group: A

Ecological site: Sandy Plains (R067BY024CO)

Minor Components

Remmit

Percent of map unit: 8 percent

Julesburg

Percent of map unit: 4 percent

Olney

Percent of map unit: 3 percent

Data Source Information

Soil Survey Area: Weld County, Colorado, Northern Part
Survey Area Data: Version 10, Sep 23, 2014