

US ROCKIES REGION

Anadarko Daily Summary Report

Well: HSR-SHARKEY 10-35

Project:COLORADO-WELD-NAD83-UTM13

Site:PLATTE 10-35 PAD

Rig name no.:BASIC 1549/1549

Event: WELL WORK EXPENSE

Start date: 9/2/2015

End date:

Spud date: 8/21/2001

Active datum: RKB @4,755.99usft (above Mean Sea Level)

UWI: 0/4/N/67/W/35/0/NWSE/6/0/0/0/0/0/0

Report no.	Report date	MD (usft)	24 hr summary
1	09/02/2015		MIRU BASIC 1549 TBG/CSG=400 BLEW DWN NDWH NUBOP EMI PROD TBG FOUND NC BAD TBG TIH W/ RBP SET @ 6800' ROLL GAS FROM WELL TOO H W/ TBG NDBOP NDWH INSTALL 5K VALVE TEST CSG TO 5000# GOOD TEST NUWH NUBOP TOO H W/ TBG NDBOP NDWH NU DUAL ENTRY EQUIP NUBOP
2	09/03/2015		OPEN STO TANK BLEW DWN TIH W/ 2000' OF 1.66" TBG C&CH MAKE ALCOMER 74 SWEEP CONTINUE TIH TO 4570' C&CH MAKING TWO ALCOMER SWEEPS SECURE WELL SDFN FOUND NO HARD SPOTS ON TIH
3	09/04/2015		SCP=20 PUMP 40 BBLS 10 PPG MUD PUH TO 4375' C&CH MIRU SANJEL PUMP 130 SKS "G" CEMENT PUH TO 1301' PUMP 140 SKS TYPE 3 CEMENT TOO H W/ 1.66" TBG NDBOP ND DUAL ENTRY EQUIP RELAND PROD CSG @ 55000# INSTALL 5K WH NUBOP SHUT AND LOCK BLIND RAMS SDFN WOC
4	09/08/2015		MIRU WARRIOR RUN CBL FROM 6200-SURFACE TOC=221' TIH TAG FILL CIRCULATE SAND OFF RBP TOO H W/ RBP PU NC XN NIPPLE TIH LAND PROD TBG W/ 229 JNTS @ 7162' BROACH TO XN NDBOP NU 5K WH TEST TOP FLANGE TO 500# GOOD TEST SWI INSTALL PLUGS RDMO