



Wellbore Dia		Axsom 1-25			
Status	Producing		Operator	Stelbar Oil Corp	
Lease	Axsom		Zone	Niobrara	
Field	DeNova		API	05-121-09281-00	
State:	Colorado		Division:		
Location	860' FSL & 660' FWL, SW/4 SW/4 Sec 25-T2S-R50W, 6th PM, Washington County, CO: ? Acre Spacing				
Reference:					
KB	4,467	TVD	3124'	Orig PBTD	3117'
GL	4,461	MTD	3124'	SN	
Casing	Weight/Grade	Depth	Cmt Sx	Hole	TOC
N/A Conductor					
8 5/8"	24#/K-55	253'	245	12 1/4"	Circ
4.5"	10.5#,K-55	3111'	150 sx 50/50 Poz	7 7/8"	TOC Unknown
Spud	10/15/1977		Top Perf	2958'	
Completion	11/11/1977		Bot Perf	2978'	
Perf: 2958'-2978', 20' @ 2 SPF, 40 holes. Stim w/ foam frac w/ 32K# sand					
Date sketch checked		6/10/15	by:	TWL	
Date tubulars checked		6/10/15	by:	TWL	
Current Tubulars					
Tubing String				Length, ft	Depth, ft
Size	Grade	# Jnts	Type		
			KBE	6.00	6.00
2 3/8	J-55	93	Plain Tbg	2914.62	2920.62
2 3/8		1	SN	1.10	2921.72
2 3/8		1	Packer	2.00	2923.72
				0.00	2923.72
					2923.72
Bottom of Tbg String:					2923.72
Rods String				Length, ft	Depth, ft
Size	Grade	# Rods			
Latitude and Longitude Location:					
Latitude:				39.846527	
Longitude:				-102.932126	