

FORM  
2

Rev  
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400834359

Date Received:

05/19/2015

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: VALLEY FARMS G

Well Number: 42C-14-06-92

Name of Operator: URS OPERATING COMPANY LLC

COGCC Operator Number: 10447

Address: 1050 17TH STREET #2400

City: DENVER State: CO Zip: 80265

Contact Name: JENNIFER LIND

Phone: (720)508-8362

Fax: ( )

Email: JLIND@URSARESOURCES.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20120125

WELL LOCATION INFORMATION

QtrQtr: SWNE Sec: 14 Twp: 6S Rng: 92W Meridian: 6

Latitude: 39.527551

Longitude: -107.630423

Footage at Surface: 2457 feet FNL/FSL FNL 1513 feet FEL/FWL FEL

Field Name: MAMM CREEK

Field Number: 52500

Ground Elevation: 5623

County: GARFIELD

GPS Data:

Date of Measurement: 06/26/2013 PDOP Reading: 2.2 Instrument Operator's Name: HOFFMANN

If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

2129 FNL 657 FEL 2129 FNL 657 FEL  
Sec: 14 Twp: 6S Rng: 92W Sec: 14 Twp: 6S Rng: 92W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: Surface Surety ID:

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

PLEASE SEE ATTACHED MINERAL LEASE MAP.

Total Acres in Described Lease: 320 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 508 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 566 Feet

Building Unit: 911 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 524 Feet

Above Ground Utility: 1517 Feet

Railroad: 5280 Feet

Property Line: 293 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 04/09/2015

## SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 330 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 508 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	523-2	320	N/2 SEC.14

## DRILLING PROGRAM

Proposed Total Measured Depth: 7520 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 330 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☐ Annular Preventor ☒ Double Ram ☐ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Other

Other Disposal Description:

PLEASE REFER TO WASTE MANAGEMENT PLAN ATTACHED TO ASSOCIATED FORM 2A.

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	74	0	60	111	60	0
SURF	12+1/4	8+5/8	32	0	1000	112	1000	0
1ST	7+7/8	4+1/21	11.6	0	7520	518	7520	

☐ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments First String / Production cement will be > 500 feet above TOG. Distance to nearest well completed in the same formation / permitted or existing well penetrating objective formation was measured to the proposed VF G 42D-14-06-92.

Pre-application Notice / Buffer Zone Notice was sent to building unit owners within 1000' of the location on 1/16/15. Preapplication certification is attached to the associated Valley Farms G Pad Form 2A (Doc #400829004).

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: \_\_\_\_\_

Is this application being submitted with an Oil and Gas Location Assessment application? \_\_\_\_\_ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: JENNIFER LIND

Title: REGULATORY ANALYST Date: 5/19/2015 Email: JLIND@URSARESOURCES.C

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 9/30/2015

Expiration Date: 09/29/2017

API NUMBER

05 045 22992 00

## **Conditions Of Approval**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### **COA Type**

### **Description**

	<p>(1) Operator shall comply with the most current revision of the Northwest Notification Policy. See attached notice.</p> <p>(2) Operator shall comply with the most current revision of the Garfield County Rulison Field Notice to Operators, with the following exception: All field notice requirements specified in that Notice to Operators are superseded by the requirements of the most current revision of the Northwest Colorado Notification Policy (see Condition of Approval #1). See attached notice.</p> <p>(3) Operator shall comply with the most current revision of the Mamm Creek Field Notice to Operators, with the following exception: All field notice requirements specified in that Notice to Operators are superseded by the requirements of the most current revision of the Northwest Colorado Notification Policy (see Condition of Approval #1). See attached notice.</p> <p>(4) Operator shall comply with the Notice to Operators Drilling Wells in the Buzzard, Mamm Creek, and Rulison fields, Garfield County and Mesa County – Procedures and Submittal Requirements for Compliance with COGCC Order Nos. 1-107, 139-56, 191-22, and 369-2 (July 8, 2010). See attached notice.</p> <p>(5) Operator shall provide cement coverage from the production casing shoe to a minimum of 200' above all Mesa Verde Group (and Ohio Creek Formation, if present) oil, gas, and water-bearing sandstone and coalbed formations. Verify production casing cement coverage with a cement bond log.</p>
--	---

## **Best Management Practices**

### **No BMP/COA Type**

### **Description**

1	Drilling/Completion Operations	Open hole resistivity log with gamma ray will be run on one well in the "first occupation" of the pad to describe the stratigraphy of the vertical section of the wellbore and to adequately verify the setting depth of the surface casing and aquifer coverage. The Drilling Completion Report - Form 5 for every well on the pad will identify which well was logged.
---	--------------------------------	--

Total: 1 comment(s)

## **Applicable Policies and Notices to Operators**

Mamm Creek Field Area Notice to Operators.
Piceance Rulison Field - Notice to Operators.
NW Colorado Notification Policy.
Bradenhead Pressure Reporting-Garfield County (Mamm Creek & Rulison Fields) Mesa County (Buzzard Field).
Notice Concerning Operating Requirements for Wildlife Protection.

## **Attachment Check List**

<b>Att Doc Num</b>	<b>Name</b>
400834359	FORM 2 SUBMITTED
400841829	DEVIATED DRILLING PLAN
400841830	WELL LOCATION PLAT
400841831	MINERAL LEASE MAP
400841832	SURFACE AGRMT/SURETY
400841833	DIRECTIONAL DATA

Total Attach: 6 Files

### **General Comments**

<b>User Group</b>	<b>Comment</b>	<b>Comment Date</b>
Permit	Corrected right to construct from SUA to lease as per opr. Final review complete.	9/29/2015 2:23:48 PM
Permit	Ready to pass.	6/15/2015 4:13:15 PM
LGD	Pass, KHW. Additional comment on the 2A.	5/9/2015 2:14:22 PM
Engineer	Evaluated existing offset oil and gas wells within 1,500 feet of this wellbore. No mitigation required.  Offset water well check: COGCC evaluated offset water wells within one mile of this proposed well's surface hole location. This information was used in addition to locally-available geophysical logs and hydrogeologic information to evaluate the adequacy of the operator's proposed surface casing setting depth. The deepest water well within one mile is 350 feet.	5/26/2015 10:27:11 AM
Permit	Passed completeness.	5/22/2015 11:23:11 AM

Total: 5 comment(s)