

**WELLBORE DIAGRAM**  
**NGL Water Solutions DJ LLC**

Planned

10/9/2015

PAG

**NGL C10A**

SHL: SWSE Sec 35-T7N-R65W

BHL: NENE Sec 35-T7N-R65W

Weld County, CO

API unassigned

K.B.= 4830

G.L.= 4808

22

**TOPS**

All listed in MD

Niobrara - 7767'

Codell - 8112'

J Sand - 8645'

Lyons - 9938'

L. Satanka- 10047'

Wolfcamp- 10384'

Amazon - 10449'

Council Grove - 10507'

Admire - 10672'

Virgil - 10737'

Missouri - 10916'

Des Moines - 11031'

Fountain - 11051'

Atoka - 11276'

TD - 11476'

9-5/8", 36# J-55 ST&C CSG Set @ 600' (12-1/4" O.H.)  
Cmt'd w/ 173 sx total

DV Tool @ 8362'  
Cmt'd w/ 888 sx Total 2nd Stage (778 sx lead, 110 sx tail)

4-1/2" tbg  
EOT & Packer @ 9843'

PBR @ TOL @ 9893'

7" 26# N-80 LT&C CSG Set @ 9938' (8-3/4" O.H.)  
Cmt'd w/ 186 sx (1st stage)

Slotted Pipe      Liner slotted with 2" by 0.040" slots on 6" centers

4-1/2" 11.6# N-80 LT&C Slotted LNR (TOL @ 9,893', EOL @ 11,476')  
(6-1/8" O.H.)

**TVD = 10,446'**  
**MD = 11,476'**