

FORM  
5Rev  
09/14

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400917536

Date Received:

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 10439

Contact Name: CAROL PRUITT

Name of Operator: CARRIZO NIOBRARA LLC

Phone: (713) 328-1000

Address: 500 DALLAS STREET #2300

Fax: (713) 328-1060

City: HOUSTON State: TX Zip: 77002

API Number 05-123-38577-00

County: WELD

Well Name: Castor

Well Number: 7-36-9-59

Location: QtrQtr: NENE Section: 36 Township: 9N Range: 59W Meridian: 6

Footage at surface: Distance: 336 feet Direction: FNL Distance: 732 feet Direction: FEL

As Drilled Latitude: 40.713430 As Drilled Longitude: -103.919900

## GPS Data:

Date of Measurement: 02/11/2014 PDOP Reading: 2.7 GPS Instrument Operator's Name: ERIC PURCELL

\*\* If directional footage at Top of Prod. Zone Dist.: 385 feet. Direction: FNL Dist.: 972 feet. Direction: FEL

Sec: 36 Twp: 9N Rng: 59W

\*\* If directional footage at Bottom Hole Dist.: 651 feet. Direction: FSL Dist.: 975 feet. Direction: FEL

Sec: 36 Twp: 9N Rng: 59W

Field Name: WILDCAT

Field Number: 99999

Federal, Indian or State Lease Number: 9821.8

Spud Date: (when the 1st bit hit the dirt) 12/08/2013 Date TD: 12/16/2013 Date Casing Set or D&amp;A: 12/13/2013

Rig Release Date: 12/18/2013 Per Rule 308A.b.

## Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 10358 TVD\*\* 6001 Plug Back Total Depth MD 10358 TVD\*\* 6001

Elevations GR 4890 KB 4907 Digital Copies of ALL Logs must be Attached per Rule 308A ☐

## List Electric Logs Run:

MWD W/ GAMMA RAY

## CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	16	36.9	0	60	8	0	60	VISU
SURF	12+1/4	9+5/8	36	0	1,400	546	1,400	1,400	VISU
1ST	8+3/4	7	23	0	6,053	535	558	6,053	CBL
1ST LINER	6+1/8	4+1/2	11.6	5326	10,348				

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

## FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	3,428	3,706	NO	NO	
SUSSEX	3,951	4,196	NO	NO	
SHARON SPRINGS	5,860	5,955	NO	NO	
NIOBRARA	5,955	10,358	NO	NO	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: CAROL PRUITT

Title: REGULATORY COMPLIANCE

Date: \_\_\_\_\_

Email: CAROL.PRUITT@CRZO.NET

## Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400917600	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400917603	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400917569	PDF-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400917570	LAS-MEASUREMENT/LOGGING WHILE DRILLING	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400917572	PDF-	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400917598	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

### General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)