

FORM
2
Rev
08/13

State of Colorado
Oil and Gas Conservation Commission
1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:
400871253

APPLICATION FOR PERMIT TO:

Drill Deepen Re-enter Recomplete and Operate

Date Received:
07/30/2015

TYPE OF WELL OIL GAS COALBED OTHER _____
ZONE TYPE SINGLE ZONE MULTIPLE ZONES COMMINGLE ZONES

Refilling
Sidetrack

Well Name: LAND Well Number: 37N-32HZ
Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP COGCC Operator Number: 47120
Address: P O BOX 173779
City: DENVER State: CO Zip: 80217-3779
Contact Name: Ronett Powers Phone: (720)929-6759 Fax: (720)929-7759
Email: ronett.powers@anadarko.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20010124

WELL LOCATION INFORMATION

QtrQtr: NWNE Sec: 32 Twp: 2N Rng: 66W Meridian: 6
Latitude: 40.099276 Longitude: -104.797724

Footage at Surface: 947 feet FNL/FSL FNL 1705 feet FEL/FWL FEL

Field Name: WATTENBERG Field Number: 90750

Ground Elevation: 4910 County: WELD

GPS Data:
Date of Measurement: 03/24/2015 PDOP Reading: 1.3 Instrument Operator's Name: ROB WILSON

If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FEL/FWL
119 FNL 1648 FEL 50 FSL 1595 FEL
Sec: 32 Twp: 2N Rng: 66W Sec: 32 Twp: 2N Rng: 66W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: Fee State Federal Indian

The Surface Owner is: is the mineral owner beneath the location.
(check all that apply) is committed to an Oil and Gas Lease.
 has signed the Oil and Gas Lease.
 is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: Fee State Federal Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: _____ Surface Surety ID: _____

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Township 2 North, Range 66 West, 6th P.M.

Section 32: NW/4NE/4, except right of way as granted by instrument recorded in Book 1090, Page 290, Weld County Records; N/2NW/4, excepting therefrom parcels conveyed by deeds recorded in Book 571, Page 371; Book 620, Page 579; Book 577, Page 575, and Book 1078, Page 239, Weld County records; also excepting right of way of Union Pacific Railroad Company, and right of way as conveyed by instrument recorded in Book 1090, Page 290, Weld County records; also except right of way granted by instrument recorded in Book 1226, Page 65, Weld County records.
Weld County, Colorado

Total Acres in Described Lease: 95 Described Mineral Lease is: Fee State Federal Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 1178 Feet
Building Unit: 1491 Feet
High Occupancy Building Unit: 4523 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 942 Feet
Above Ground Utility: 908 Feet
Railroad: 1841 Feet
Property Line: 305 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: Buffer Zone
 Exception Zone
 Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 270 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 996 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

UNIT CONFIGURATION:

02N66W SEC 29 S2SE
02N66W SEC 32 E2
01N66W SEC 05 N2NE

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		480	GWA

DRILLING PROGRAM

Proposed Total Measured Depth: 12899 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 80 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: Annular Preventor Double Ram Rotating Head None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Please see Comments section. Disposal description will not fit in space provided.

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	13+1/2	9+5/8	36	0	1600	630	1600	0
1ST	7+7/8	5+1/2	17	0	12889	1328	12889	0

Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- Rule 318A.a. Exception Location (GWA Windows).
- Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

- Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

OTHER DISPOSAL DESCRIPTION:

Drilling fluids disposal: KMG will reuse water-based drilling fluids to the maximum extent possible, at which point they will either be land applied or taken to a licensed, commercial disposal site; the decision will be based upon laboratory analysis of fluids. KMG will reuse oil-based drilling fluids to the maximum extent possible, at which point they will be returned to the fluids manufacturer for reconditioning or disposal at a licensed, commercial disposal site.

Cuttings disposal: Water-based cuttings will be disposed of using a Centralized E&P Waste Management facility or a private spread field, depending on what is feasible at the time of drilling. Oil-based cuttings will be disposed of offsite and at a licensed, commercial disposal site.

This proposed well will have a treated interval less than one hundred fifty (150) feet from the treated interval of another well and is subject to COGCC Rule 317.r. The well(s) belong to Kerr-McGee and will have treated intervals within one hundred fifty (150) feet of this proposed well:

- KEITH A CARTER UNIT 1
- FEHRN 7-32
- FEHRN 25-32
- CARTER 10-32
- CARTER 23-32
- CARTER 36-32
- CARTER 15-32

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Ronett Powers

Title: Regulatory Analyst II Date: 7/30/2015 Email: djregulatory@anadarko.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: *Matthew Lee* Director of COGCC Date: 10/18/2015

Expiration Date: 10/17/2017

API NUMBER
05 123 42301 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

<u>COA Type</u>	<u>Description</u>
	Operator acknowledges the proximity of the listed wells. Operator agrees to: provide mitigation option 1 or 2 (per the DJ Basin Horizontal Offset Policy) to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, and submit a Form 42 ("OFFSET MITIGATION COMPLETED") stating that appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well. Keith A Carter Unit 1 API#123-07767); Pacheco Heirs Gas Unit 1 API#-123-08406
	1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU. 2) Comply with Rule 317.j and provide cement coverage from end of 5.5" casing to a minimum of 200' above Niobrara and from 200' below the Sussex to 200' above Sussex. Verify coverage with cement bond log.

Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Planning	This proposed oil and gas location is located in a rural rangeland area. The nearest building unit is located 1491' away.
2	Drilling/Completion Operations	Kerr McGee acknowledges and will comply with the COGCC Policy for Bradenhead Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
3	Drilling/Completion Operations	Anti-Collision: Kerr-McGee will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within one hundred fifty (150) feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators within one hundred fifty (150) feet prior to drilling.
4	Drilling/Completion Operations	317.p Logging Program: One of the first wells drilled on the pad will be logged with Cased-hole Pulsed Neutron Log with Gamma Ray Log from TD into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run in that well and have those logs attached. The Form 5 for each well shall clearly state "No open-hole logs were run" and shall reference the Rule 317.p Exception granted for the well.

Total: 4 comment(s)

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.

Attachment Check List

Att Doc Num	Name
1696616	OPEN HOLE LOGGING EXCEPTION
400871253	FORM 2 SUBMITTED
400877425	OffsetWellEvaluations Data
400877436	DIRECTIONAL DATA
400877437	EXCEPTION LOC REQUEST
400877438	DEVIATED DRILLING PLAN
400877439	WELL LOCATION PLAT
400877440	PROPOSED SPACING UNIT
400877442	SURFACE AGRMT/SURETY
400877443	LEASE MAP
400882857	EXCEPTION LOC WAIVERS
400915114	SURFACE CASING CHECK
400915115	OFFSET WELL EVALUATION

Total Attach: 13 Files

General Comments

User Group	Comment	Comment Date
Permit	Final Review Completed.	10/15/2015 11:26:57 AM
Engineer	Changed distance to nearest well penetrating objective formation from 139' to 80' (Keith A Carter Unit #1 123-07767).	10/14/2015 4:59:12 PM
Engineer	Evaluated offset wells for adequate isolation. Emailed operator.	10/9/2015 12:07:26 PM
Permit	Attached corrected Open Hole Logging Exception request letter. Permitting Review Complete.	10/7/2015 9:22:44 AM
Permit	ON HOLD: Requesting a corrected Open Hole Logging Exception request letter.	9/30/2015 3:18:55 PM
Permit	Operator requested Exception to Open Hole Logging Rule 317.p. See attached.	9/30/2015 3:18:54 PM
LGD	These wells have been reviewed and approved by the City. The City requires that Kerr-McGee enter into an off-site improvements agreement for these wells.	8/31/2015 8:39:09 AM
Permit	Passed completeness.	8/19/2015 6:46:33 AM
Permit	Returned to draft. 1.) Operator's Wellbore Integrity Contact email is blank. 2.) Exception Location Waiver does not follow the guidance document.	3/6/2015 2:29:23 PM

Total: 9 comment(s)