

FORM
5A

Rev
06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400921207

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 10439
2. Name of Operator: CARRIZO NIOBRARA LLC
3. Address: 500 DALLAS STREET #2300
City: HOUSTON State: TX Zip: 77002
4. Contact Name: Jeff Annable
Phone: (303) 928-7128
Fax: (303) 2185678
Email: regulatory@petro-fs.com

5. API Number 05-123-38584-00
6. County: WELD
7. Well Name: Bringelson Ranch
Well Number: 7-20-9-58
8. Location: QtrQtr: SWSW Section: 20 Township: 9N Range: 58W Meridian: 6
9. Field Name: WILDCAT Field Code: 99999

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 05/05/2014 End Date: 05/06/2014 Date of First Production this formation: 05/19/2014

Perforations Top: 6056 Bottom: 10181 No. Holes: Hole size:

Provide a brief summary of the formation treatment: Open Hole: ☒

Fracture stimulated through a 15 stage port and packer system with 3,280,390 lbs of sand and 51,533 bbls of fresh water.

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 51533 Max pressure during treatment (psi): 5377

Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal): 8.90

Type of gas used in treatment: Min frac gradient (psi/ft): 0.78

Total acid used in treatment (bbl): Number of staged intervals: 15

Recycled water used in treatment (bbl): Flowback volume recovered (bbl): 16490

Fresh water used in treatment (bbl): 51533 Disposition method for flowback: DISPOSAL

Total proppant used (lbs): 3280390 Rule 805 green completion techniques were utilized: ☐

Reason why green completion not utilized: PIPELINE

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 05/19/2014 Hours: 24 Bbl oil: 156 Mcf Gas: 0 Bbl H2O: 907

Calculated 24 hour rate: Bbl oil: 156 Mcf Gas: 0 Bbl H2O: 907 GOR: 0

Test Method: 24 Hour Flowbac Casing PSI: 420 Tubing PSI: Choke Size: 24/64

Gas Disposition: Gas Type: Btu Gas: 0 API Gravity Oil: 38

Tubing Size: 2 + 3/8 Tubing Setting Depth: 5700 Tbg setting date: 06/06/2014 Packer Depth: 5694

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

Gas wasn't produced during the test period but is being produced currently. The gas has since been analyzed and the analysis is attached as OTHER.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jeff Annable

Title: Regulatory Analyst Date: _____ Email regulatory@petro-fs.com
:

Attachment Check List

Att Doc Num **Name**

400921241	OTHER
400921243	WELLBORE DIAGRAM

Total Attach: 2 Files

General Comments

User Group **Comment** **Comment Date**

--	--	--

Total: 0 comment(s)