

US ROCKIES REGION

Anadarko Daily Summary Report

Well: DEVON 9-8

Project:COLORADO-WELD-NAD83-UTM13

Site:DEVON 9-8

Rig name no.:LEED ENERGY/721

Event: ABANDONMENT

Start date: 9/24/2015

End date:

Spud date: 11/12/2004

Active datum: RKB @4,865.99usft (above Mean Sea Level)

UWI: 0/3/N/66/W/8/0/SENE/6/0/S/-2170/E/0/500/0/0

Report no.	Report date	MD (usft)	24 hr summary
1	09/24/2015		MIRU LEED 721, ND TA VALVE, NU WH, NU BOP, TIH 214JTS 2.375" TBG, CIRCULATE SAND OFF RBP, RELEASE RBP & TOOHD RBP, SDFN
2	09/25/2015		TIH 215JTS 2.375" TBG, CIRCULATE SAND OFF RBP, RELEASE RBP & TOOHD RBP, RIH W/3.75" GAUGE RING TO 7020', RIH SET CIBP @ 7010', TIH W/222JTS 2.375" TBG + 10' SUB (EOT @ 7006'), CIRCULATE GAS OUT-FULL RETURNS, PT CIBP TO 1000# FOR 15MIN, SDFN
3	09/28/2015		RU SANJEL, PUMP 25 SX CMT @ 7010' FOR NIO PLUG. PU TO 5793', CIRC CLEAN FULL RETURNS. PU TO 4480', PUMP 35 SX SANJEL FOR SUSSEX PLUG. PU TO 3776', CIRC CLEAN FULL RETURNS. WOC 4 HRS, TIH W/20JTS 2.375"TBG NO TAG, PUH TO 3776", CIRCULATE, SDFN
4	09/29/2015		TIH TAG TOC @ 4055', TOOHD. RIH TO 1090' & CUT CSG, ND BOP, ND WH, UNLAND CSG W/30,000LBS, NU BOP, CIRC-FULL RETURNS, POOH & LD 4-1/2" CSG. TIH TO 1197' W/ 2-3/8" TBG, PUMP 195 SX TYPE III SANJEL. PUH TO 96' & CIRC CLEAN. TOOHD, SWI, SDFN.
5	09/30/2015		TIH W/16JTS 2.375"TBG TAG TOC @ 503', TOOHD LD TBG, ND BOP, ND WH, RIH W/ 8-5/8" CIBP, SET @ 80', PT TO 1000 PSI FOR 15MIN-GOOD TEST, RDMO LEED 721 TO PLATTEVILLE 23-19A
6	10/14/2015		Exposed surface casing. Cut casing 6' below GL. Tagged @ 62'. Filled casing stub with 33 bags 5000 psi cement. Capped casing with a metal plate containing well info. Backfilled.