

FORM
2
Rev
08/13

State of Colorado
Oil and Gas Conservation Commission
1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:
400923330
(SUBMITTED)

APPLICATION FOR PERMIT TO:

- Drill Deepen Re-enter Recomplete and Operate

Date Received:

TYPE OF WELL OIL GAS COALBED OTHER _____ Refilling
ZONE TYPE SINGLE ZONE MULTIPLE ZONES COMMINGLE ZONES Sidetrack

Well Name: Horsetail Well Number: 08C-1738
Name of Operator: WHITING OIL & GAS CORPORATION COGCC Operator Number: 96155
Address: 1700 BROADWAY STE 2300
City: DENVER State: CO Zip: 80290
Contact Name: Michael Brown Phone: (307)237-9310 Fax: ()
Email: ml_brown@bresnan.net

RECLAMATION FINANCIAL ASSURANCE
Plugging and Abandonment Bond Surety ID: 20030110

WELL LOCATION INFORMATION
QtrQtr: NENW Sec: 8 Twp: 10N Rng: 57W Meridian: 6
Latitude: 40.859925 Longitude: -103.777244
Footage at Surface: 330 feet FNL/FSL FNL 2261 feet FEL/FWL FWL
Field Name: WILDCAT Field Number: 99999
Ground Elevation: 4914 County: WELD
GPS Data:
Date of Measurement: 12/09/2014 PDOP Reading: 1.9 Instrument Operator's Name: Dallas Nielsen
If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**
Footage at Top of Prod Zone: FNL/FSL FNL 654 FNL 1797 FWL Bottom Hole: FNL/FSL FSL 100 FSL 1650 FWL
Sec: 8 Twp: 10N Rng: 57W Sec: 17 Twp: 10N Rng: 57W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT
Surface Ownership: Fee State Federal Indian
The Surface Owner is: is the mineral owner beneath the location.
(check all that apply) is committed to an Oil and Gas Lease.
 has signed the Oil and Gas Lease.
 is the applicant.
The Mineral Owner beneath this Oil and Gas Location is: Fee State Federal Indian
The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes
The right to construct the Oil and Gas Location is granted by: oil and gas lease
Surface damage assurance if no agreement is in place: _____ Surface Surety ID: _____

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Tract 1 6th PM T10N R57W
Sec 7: Gr acs: 312.4500 Net acs: 312.4500
L3(36.18), L4(36.27), E2SW, W2SE, E2SE
Sec 18: Gr acs: 160.0000 Net acs: 160.0000
NE
Tract 2 6th PM T10N R57W
Sec 7: Gr acs: 232.0900 Net acs: 232.0900
L1(36.00), L2(36.09), E2NW, E2NE
Tract 3 6th PM T10N R57W
Sec 8: Gr acs: 480.0000 Net acs: 480.0000
W2, W2E2
Sec 17: Gr acs: 80.0000 Net acs: 80.0000
N2NW

Total Acres in Described Lease: 1264 Described Mineral Lease is: Fee State Federal Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 5280 Feet
Building Unit: 5280 Feet
High Occupancy Building Unit: 5280 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 330 Feet
Above Ground Utility: 2310 Feet
Railroad: 5280 Feet
Property Line: 330 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: Buffer Zone
 Exception Zone
 Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 293 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 100 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	535-658	1280	All S8, All S17

DRILLING PROGRAM

Proposed Total Measured Depth: 16170 Feet
 Distance to nearest permitted or existing wellbore penetrating objective formation: 293 Feet (Including plugged wells)
 Will a closed-loop drilling system be used? Yes
 Is H2S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H2S Drilling Operations Plan)
 Will salt sections be encountered during drilling? No
 Will salt based (>15,000 ppm Cl) drilling fluids be used? No
 Will oil based drilling fluids be used? No
 BOP Equipment Type: Annular Preventor Double Ram Rotating Head None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal
 Cuttings Disposal: ONSITE Cuttings Disposal Method: Other
 Other Disposal Description:

 Beneficial reuse or land application plan submitted? _____
 Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	65	0	80	179	80	0
SURF	13+1/2	9+5/8	36	0	1600	711	1600	0
1ST	8+3/4	7	29	0	6289	421	6289	0
1ST LINER	6	4+1/2	11.6	5471	16170			

Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

- Check all that apply:
- Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
 - Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
 - Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
 - Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
 - Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

- Check all that apply:
- Rule 318A.a. Exception Location (GWA Windows).
 - Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

Rule 318.c. Exception Location from Rule or Spacing Order Number _____

Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments _____

This application is in a Comprehensive Drilling Plan _____ No _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes _____

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Michael Brown

Title: Agent _____ Date: _____ Email: ml_brown@bresnan.net

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC _____ Date: _____

Expiration Date: _____

API NUMBER

05

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Best Management Practices

No	BMP/COA Type	Description
1	Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with oil and gas development throughout the State of Colorado. BMPs will be constructed as necessary to prevent stormwater from leaving the construction site. BMPs used will vary according to the location, and will remain until the pad is reclaimed.
2	Material Handling and Spill Prevention	<p>Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with oil and gas operations throughout the State of Colorado.</p> <ul style="list-style-type: none"> • Materials and fluids will be stored in a neat and orderly fashion. • Waste will be collected regularly and disposed of at an offsite facility. • Prompt cleanup is required of spills to minimize waste materials entering the stormwater runoff. • Drip pans will be used during fueling and maintenance to contain spills or leaks. • Cleanup of trash and discarded material will be done at the end of the work day. • Cleanup will consist of monitoring the road, location and any other work areas. • Material to be cleaned up includes trash, scrap, and contaminated soil.
3	Drilling/Completion Operations	One of the first wells drilled on the pad will be logged with an open-hole resistivity log with gamma-ray from TD to into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on the production casing (or intermediate casing if production liner is run). All wells on the pad will have the horizontal portion of the wellbore logged with a measured-while-drilling log with gamma-ray. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "No open-hole logs were run." The Form 5 for a well without open-hole logs shall clearly identify (by API#, well name & number) the well in which open-hole logs were run.

Total: 3 comment(s)

Attachment Check List

Att Doc Num	Name
400926681	OffsetWellEvaluations Data
400926684	DIRECTIONAL DATA
400926685	WELL LOCATION PLAT
400926690	DEVIATED DRILLING PLAN
400926691	DEVIATED DRILLING PLAN
400926693	DRILLING PLAN

Total Attach: 6 Files

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)