

**FORM
INSP**Rev
05/11**State of Colorado
Oil and Gas Conservation Commission**1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

DE	ET	OE	ES
----	----	----	----

Inspection Date:
10/30/2015Document Number:
675202180Overall Inspection:
SATISFACTORY**FIELD INSPECTION FORM**

Location Identifier	Facility ID	Loc ID	Inspector Name:	On-Site Inspection	2A Doc Num:
	442548	442549	CONKLIN, CURTIS	<input type="checkbox"/>	

Operator Information:OGCC Operator Number: 10433Name of Operator: PICEANCE ENERGY LLCAddress: 1512 LARIMER STREET #1000City: DENVER State: CO Zip: 80202

- ☐ THIS IS A FOLLOW UP INSPECTION
- ☐ FOLLOW UP INSPECTION REQUIRED
- ☒ NO FOLLOW UP INSPECTION REQUIRED
- ☐ INSPECTOR REQUESTS FORM 42 WHEN CORRECTIVE ACTIONS ARE COMPLETED

Contact Information:

Contact Name	Phone	Email	Comment
Bankert, Wayne	(970) 683-5419	wbankert@laramie-energy.com	Senior Regulatory & Environmental Coordinator

Compliance Summary:QtrQtr: NESW Sec: 28 Twp: 9S Range: 93W**Inspector Comment:**Drilling and surface cement**Related Facilities:**

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status	
442546	WELL	XX	07/21/2015		077-10246	Piceance Fed 28-11E	XX	<input type="checkbox"/>
442547	WELL	XX	07/21/2015		077-10247	Piceance Fed 28-05E	XX	<input type="checkbox"/>
442548	WELL	XX	07/21/2015		077-10248	Piceance Fed 28-14E	DG	<input checked="" type="checkbox"/>
442550	WELL	XX	07/21/2015		077-10249	Piceance Fed 28-13E	XX	<input type="checkbox"/>
442551	WELL	DG	10/09/2015		077-10250	Piceance Fed 28-21E	DG	<input type="checkbox"/>
442553	WELL	XX	07/21/2015		077-10251	Piceance Fed 28-08E	XX	<input type="checkbox"/>
442555	WELL	XX	07/21/2015		077-10252	Piceance Fed 28-06E	XX	<input type="checkbox"/>
442556	WELL	XX	07/21/2015		077-10253	Piceance Fed 28-12E	XX	<input type="checkbox"/>
442558	WELL	DG	10/20/2015		077-10254	Piceance Fed 28-19E	DG	<input type="checkbox"/>
442559	WELL	XX	07/21/2015		077-10255	Piceance Fed 28-09E	XX	<input type="checkbox"/>
442560	WELL	DG	10/14/2015		077-10256	Piceance Fed 28-20E	DG	<input type="checkbox"/>
442562	WELL	XX	07/21/2015		077-10257	Piceance Fed 28-15E	XX	<input type="checkbox"/>
442563	WELL	DG	10/24/2015		077-10258	Piceance Fed 28-18E	DG	<input type="checkbox"/>
442564	WELL	XX	07/21/2015		077-10259	Piceance Fed 28-17E	XX	<input type="checkbox"/>
442565	WELL	XX	07/21/2015		077-10260	Piceance Fed 28-10E	XX	<input type="checkbox"/>
442566	WELL	XX	07/21/2015		077-10261	Piceance Fed 28-07E	XX	<input type="checkbox"/>
442567	WELL	XX	07/21/2015		077-10262	Piceance Fed 28-16E	XX	<input type="checkbox"/>

Equipment:Location Inventory

Inspector Name: CONKLIN, CURTIS

Special Purpose Pits: _____	Drilling Pits: _____	Wells: <u>17</u>	Production Pits: _____
Condensate Tanks: <u>8</u>	Water Tanks: _____	Separators: <u>5</u>	Electric Motors: _____
Gas or Diesel Mortors: _____	Cavity Pumps: _____	LACT Unit: _____	Pump Jacks: _____
Electric Generators: _____	Gas Pipeline: _____	Oil Pipeline: _____	Water Pipeline: _____
Gas Compressors: _____	VOC Combustor: <u>1</u>	Oil Tanks: _____	Dehydrator Units: _____
Multi-Well Pits: _____	Pigging Station: _____	Flare: _____	Fuel Tanks: _____

Location

<u>Lease Road:</u>				
Type	Satisfactory/Action Required	comment	Corrective Action	Date
Access	SATISFACTORY			

<u>Signs/Marker:</u>				
Type	Satisfactory/Action Required	Comment	Corrective Action	CA Date
TANK LABELS/PLACARDS	SATISFACTORY			

Emergency Contact Number (S/A/V): SATISFACTORY Corrective Date: _____

Comment: _____

Corrective Action: _____

<u>Spills:</u>				
Type	Area	Volume	Corrective action	CA Date
<input type="checkbox"/> Multiple Spills and Releases?				

<u>Venting:</u>	
Yes/No	Comment
NO	

<u>Flaring:</u>				
Type	Satisfactory/Action Required	Comment	Corrective Action	CA Date

Predrill

Location ID: 442548

Site Preparation:

Lease Road Adeq.: _____ Pads: _____ Soil Stockpile: _____

S/A/V: _____

Corrective Action: _____ Date: _____ CDP Num.: _____

Form 2A COAs:

Group	User	Comment	Date
OGLA	kubeczkd	Operator shall pressure test pipelines in accordance with Rule 1101.e.(1) prior to putting into initial service any temporary surface or permanent buried pipelines and following any reconfiguration of the pipeline network. Operator will utilize, to the extent practical, all existing access and other public roads, and/or existing pipeline right-of-ways, when placing/routing the surface pipelines. This will reduce surface disturbance and fragmentation of wildlife habitat in the area.	07/13/2015

OGLA	kubeczkd	Notify the COGCC 48 hours prior to start of pad construction, rig mobilization, spud, pipeline testing, start of hydraulic stimulation operations, and start of flowback operations (if different than the start of hydraulic stimulation operations) using Form 42 (the appropriate COGCC individuals will automatically be email notified, including the LGD for hydraulic stimulation operations).	07/13/2015
OGLA	kubeczkd	<p>Operator must ensure secondary containment for any volume of fluids contained at tank site during operations (as shown on the Location Drawing and the Construction Layout Drawings attachments); including, but not limited to, construction of a berm or diversion dike, diversion/collection trenches within and/or outside of berms/dikes, site grading, or other comparable measures (i.e., best management practices (BMPs) associated with stormwater management) sufficiently protective of nearby surface water. Any berm constructed at the well pad location will be stabilized, inspected at regular intervals (at least every 14 days and after significant precipitation events, and/or in accordance with CDPHE regulations), and maintained in good condition.</p> <p>The location is in an area of moderate to high run-on/run-off potential; therefore standard stormwater BMPs must be implemented at this location prior to construction, throughout construction, drilling, and completion operations to insure compliance with CDPHE and COGCC requirements and to prevent any stormwater run-on and /or stormwater run-off.</p> <p>The access road will be constructed and maintained as to not allow any sediment to migrate from the access road to nearby surface water or any drainages leading to surface water.</p> <p>Strategically apply fugitive dust control measures, including enforcing established speed limits on private roads, to reduce fugitive dust and coating of vegetation and deposition in water sources.</p> <p>Berms or other containment devices shall be constructed to be sufficiently impervious (corrugated steel with poly liner) to contain any spilled or released material around crude oil, condensate, and produced water storage tanks.</p>	07/13/2015
OGLA	kubeczkd	<p>The moisture content of drill cuttings managed onsite shall be kept as low as practicable to prevent accumulation of liquids greater than de minimis amounts. After drilling and completion operations have been completed, the drill cuttings that will remain on the well pad location (cuttings management area, the cut portion of the pad, cuttings trench, dry cuttings drilling pit), must meet the applicable standards of Table 910-1. Land-farming of E&P waste is prohibited on the location; however, this shall not preclude onsite disposal of E&P waste in accordance with COGCC Rules and permit conditions. After the drill cuttings have been amended (if necessary) and placed on the well pad, sampling frequency of the drill cuttings (to be determined by the operator) shall be representative of the material left on location. No offsite disposal of cuttings to another oil and gas location shall occur without prior approval of a an amended Waste Management Plan (submitted via a Form 4 Sundry Notice) specifying disposal location and waste characterization method. Commercial disposal of drill cuttings will only require notification to COGCC via a Form 4 Sundry Notice.</p> <p>If the wells are to be hydraulically stimulated, flowback and stimulation fluids must be sent to tanks, separators, or other containment/filtering equipment before the fluids can be placed into any pipeline or storage vessel located on the well pad; or into tanker trucks for offsite disposal. The flowback and stimulation fluid tanks, separators, or other containment/filtering equipment must be placed on the well pad in an area constructed to be sufficiently impervious to contain any spilled or released material.</p> <p>Potential odors associated with the completions process and/or with long term production operations must be controlled/mitigated.</p>	07/13/2015

S/A/V: _____ **Comment:** Notifications have been received.

CA: _____

Date: _____

Wildlife BMPs:

BMP Type	Comment
Wildlife	<p>PICEANCE ENERGY, LLC</p> <p>Best Management Practices (BMP's) To Reduce Impacts to Wildlife on the Piceance 28-10 Pad For Operations in Sec. 28, Twn. 9S, Rng. 93W 6th PM Mesa County, CO</p> <p>COGCC Mapping indicates: ** NO RSO (Restricted Surface Occupancy) on the Piceance 28-10 Pad ** SWH (Black Bear) on the Piceance 28-10 Pad Note: COGCC Order 399-7 Excuses Piceance Energy from consultation with CDOW (CPW) contained in rule 306c.</p> <p>In an effort to minimize the impacts to wildlife, the following BMP's are part of Piceance Energy's (PE) standard operating procedures for drilling and operations within the Piceance Basin. This list is a partial of PE's policy.</p> <p>Initial Stages for Infrastructure and Roads</p> <p>1. Road design and General</p> <ul style="list-style-type: none"> - No firearms, no dogs on location, and no feeding of wildlife. - Minimize the amount of traffic on lease roads within 3 hours of sunrise and sunset. - Use existing routes as much as possible to avoid new disturbance and habitat fragmentation and minimize new road construction. - Maximize the topography as much as possible in designing roads to reduce, visual, noise, impacts, etc. - Participate in road sharing agreements with other Operators when possible. - Design and surface roads based on the traffic, speed, and type of vehicles to reduce, dust, mud, and environmental damage. - Locate roads away from riparian areas and bottoms of drainages as much as possible or re-route entirely. - Obtain Army Corp of Engineer Permits for any stream crossings prior to construction. - Analyze crossings and flow characteristics to determine the best method of crossing, (i.e. culvert, bridge, or low water). - Armor all stream crossings to reduce erosion and to comply with Stormwater Requirements. - Implementation of fugitive dust control measures including but not limited to water or magnesium chloride applications, and road surfacing. - Limit traffic to the minimum needed for safe and efficient operations. - No driving or parking off of disturbed areas. - Install and use locked gates or other means when allowed by landowner or Federal Agencies to prevent unauthorized travel on roads and rights-of ways. <p>2. Well pad design and location</p> <ul style="list-style-type: none"> - Locate well pads to maximize directional drilling practices. PE currently plans and attempts to locate pads for the maximum number of wells which can safely be developed from each pad. This is normally 16-20 wells per pad which equates to roughly 4 well pads per section. - Design each location to accommodate both current and future gas production. - Locate well pads to minimize disturbance yet maximize use to reduce surface impacts. - Review State and Federal GIS mapping to avoid Sensitive Wildlife Habitat (SWH), Restricted Surface Occupancy (RSO) areas, steep slopes, etc., as much as possible with roads and pad location. - Design and install gathering lines within the disturbed area of new roads and adjacent to as much as possible to reduce disturbance construction. - Design Rights-of Way widths to the minimum needed for safe and efficient construction of pipelines - Remote Telemetry for production operations <p>3. Drilling and Production Operations</p> <ul style="list-style-type: none"> - Implement remote telemetry in all operations - Where topographically possible and subject to landowner approval, use centralized water gathering and transportation systems.

- Install exclusionary devices to prevent bird and other wildlife access to equipment stacks, vents, and openings.
- Locate facilities to minimize visual effects (e.g. paint color, screening, etc.)
- PE implements a dewatering system in its operations. No fluid pits are constructed or used during drilling or completion operations.
- PE implements an aggressive weed management program. PE incorporates and uses the BLM Colorado River Valley Field Office's "Noxious and Invasive Weed Management Plan for Oil and Gas Operators- March 2007" for all operations. Each spring, Piceance Energy inventories all pads, roads, and pipelines to insure no noxious weeds have been introduced. If noxious weeds are found, the county will be notified and the weeds will be treated. Weeds are continuously monitored and treated throughout the growing season. Only herbicides approved by the EPA and State are used by certified weed applicators.

4. Reclamation

- Strip and segregate topsoil from other soil horizons during pad, road, and pipeline construction.
- Minimize topsoil degradation by windrowing no higher than 5 feet when possible.
- Immediately seed topsoil to reduce erosion and prevent weed establishment and maintain soil microbial activity.
- Use only certified weed free native seed mixes, unless recommended otherwise by Federal Agencies or the Landowner.
- Use locally adapted seed when available.
- Use diverse seed mixes to mirror the surrounding area unless recommended otherwise by Federal Agencies or the Landowner.
- Monitor re-vegetation success until a minimum of 75% of preferred perennial plant cover (no weeds) is established.
- Perform "interim" reclamation on all disturbed areas not needed for active producing operations.
- If possible, conduct interim and final reclamation during optimum periods (e.g. late fall/early winter or early spring).
- If needed, fence reclaimed areas to minimize livestock/wildlife impact until plant species have are capable of sustaining grazing.

PICEANCE ENERGY, LLC
 BMPS FOR
 Sensitive Wildlife Habitat and Restricted Surface Occupancy
 Areas Specific to Piceance Energy, LLC
 Operations within the Piceance Basin
 Mesa County, CO

Sensitive Wildlife Habitat (SWH)

Black Bear

- Initiate a food and waste/refuse management program that uses bear-proof food storage containers and trash receptacles.
- Initiate an education program that reduces bear conflicts.
- Establish policy to prohibit keeping food and trash in sleeping quarters.
- Establish policy to support enforcement of state prohibition on feeding of black bear.
- Report bear conflicts immediately to CPW .

Signature /s/ Wayne P. Bankert Date 5/8/2014
 Wayne P. Bankert
 Senior Reg. & Env. Coordinator

Storm Water/Erosion
 Control

CDPHE Stormwater Certification Number COR03K454 for North Vega Project Area will include this location.

S/AV: _____ **Comment:** _____
CA: _____ **Date:** _____

Stormwater:**Comment:****Staking:****On Site Inspection (305):**Surface Owner Contact Information:

Name: _____ Address: _____

Phone Number: _____ Cell Phone: _____

Operator Rep. Contact Information:

Landman Name: _____ Phone Number: _____

Date Onsite Request Received: _____ Date of Rule 306 Consultation: _____

Request LGD Attendance: _____

LGD Contact Information:

Name: _____ Phone Number: _____ Agreed to Attend: _____

Summary of Landowner Issues:Summary of Operator Response to Landowner Issues:Onsite Inspection Memorandum Summarizing Discussions at Inspection as Attachment:**Facility**

Facility ID: 442548 Type: WELL API Number: 077-10248 Status: XX Insp. Status: DG

Well Drilling**Rig:** Rig Name: Patterson 306 Pusher/Rig Manager: Rodger Foster

Permit Posted: SATISFACTORY Access Sign: SATISFACTORY

Well Control Equipment:

Pipe Ram: _____ Blind Ram: _____ Hydril Type: _____

Pressure Test BOP: _____ Test Pressure PSI: _____ Safety Plan: _____

Drill Fluids**Management:**

Lined Pit: _____ Unlined Pit: _____ Closed Loop: YES Semi-Closed Loop: _____

Multi-Well: YES Disposal Location: _____

Comment:

Cement**Cement Contractor**

Contractor Name: _____

Contractor Phone: _____

Surface Casing

Cement Volume (sx): 25 bbls to surface

Circulate to Surface: YES

Cement Fall Back: NO

Top Job, 1" Volume: _____

Intermediate Casing

Cement Volume (sxs): _____

Good Return During Job: _____

Production Casing

Cement Volume (sx): _____

Good Return During Job: _____

Plugging Operations

Depth Plugs(feet range): _____

Cement Volume (sx): _____

Good Return During Job: _____

Cement Type: _____

Comment: Shoe at 1570'

Environmental**Spills/Releases:**

Type of Spill: _____ Description: _____ Estimated Spill Volume: _____

Comment: _____

Corrective Action: _____ Date: _____

Reportable: _____ GPS: Lat _____ Long _____

Proximity to Surface Water: _____ Depth to Ground Water: _____

Water Well:

DWR Receipt Num: _____ Owner Name: _____ GPS : _____ Lat _____ Long _____

Field Parameters:

Sample Location: _____

Emission Control Burner (ECB): _____

Comment: _____

Pilot: _____ Wildlife Protection Devices (fired vessels): _____

Reclamation - Storm Water - Pit**Interim Reclamation:**

Date Interim Reclamation Started: _____ Date Interim Reclamation Completed: _____

Land Use: RANGELAND, RECREATIONAL

Comment: _____

1003a. Debris removed? _____ CM _____

CA _____ CA Date _____

Waste Material Onsite? _____ CM _____

CA _____ CA Date _____

Unused or unneeded equipment onsite? _____ CM _____
 CA _____ CA Date _____
 Pit, cellars, rat holes and other bores closed? _____ CM _____
 CA _____ CA Date _____
 Guy line anchors removed? _____ CM _____
 CA _____ CA Date _____
 Guy line anchors marked? _____ CM _____
 CA _____ CA Date _____

1003b. Area no longer in use? _____ Production areas stabilized ? _____
 1003c. Compacted areas have been cross ripped? _____
 1003d. Drilling pit closed? _____ Subsidence over on drill pit? _____
 Cuttings management: _____
 1003e. Areas no longer needed for drilling or subsequent operations for have been re-vegetated to 80% of pre-existing? _____
 Production areas have been stabilized? _____ Segregated soils have been replaced? _____

RESTORATION AND REVEGETATIONCropland

Top soil replaced _____ Recontoured _____ Perennial forage re-established _____

Non-Cropland

Top soil replaced _____ Recontoured _____ 80% Revegetation _____

1003 f. Weeds Noxious weeds? _____

Comment: _____

Overall Interim Reclamation _____

Final Reclamation/ Abandoned Location:

Date Final Reclamation Started: _____ Date Final Reclamation Completed: _____

Final Land Use: RANGELAND, RECREATIONAL

Reminder: _____

Comment: _____

Well plugged _____ Pit mouse/rat holes, cellars backfilled _____
 Debris removed _____ No disturbance /Location never built _____
 Access Roads Regraded _____ Contoured _____ Culverts removed _____
 Gravel removed _____
 Location and associated production facilities reclaimed _____ Locations, facilities, roads, recontoured _____
 Compaction alleviation _____ Dust and erosion control _____
 Non cropland: Revegetated 80% _____ Cropland: perennial forage _____
 Weeds present _____ Subsidence _____

Comment: _____

Corrective Action: _____ Date _____

Overall Final Reclamation _____ Well Release on Active Location ☐ Multi-Well Location ☐

Inspector Name: CONKLIN, CURTIS

Storm Water:						
Loc Erosion BMPs	BMP Maintenance	Lease Road Erosion BMPs	Lease BMP Maintenance	Chemical BMPs	Chemical BMP Maintenance	Comment
Compaction	Pass	Compaction	Pass			
Ditches	Pass	Culverts	Pass			
Retention Ponds	Pass	Gravel	Pass			
Berms	Pass	Check Dams	Pass			

S/A/V: SATISFACTOR
Y Corrective Date: _____

Comment: _____

CA: _____

Pits: ☒ NO SURFACE INDICATION OF PIT