

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400852326

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER _____

Refiling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Date Received:

08/31/2015

Well Name: JANE

Well Number: 1-23

Name of Operator: GRAND MESA OPERATING CO

COGCC Operator Number: 35080

Address: 1700 N. WATERFRONT PKWY BL 600

City: WICHITA

State: KS

Zip: 67206

Contact Name: MICHAEL J. REILLY

Phone: (316)265-3000

Fax: (316)265-3455

Email: PBREWER@GMOCKS.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20020080

WELL LOCATION INFORMATION

QtrQtr: SWNW Sec: 23 Twp: 3S Rng: 53W Meridian: 6

Latitude: 39.778990

Longitude: -103.292330

Footage at Surface: 1737 feet FNL/FSL FNL 184 feet FEL/FWL FWL

Field Name: WILDCAT

Field Number: 99999

Ground Elevation: 4954

County: WASHINGTON

GPS Data:

Date of Measurement: 06/05/2015 PDOP Reading: 1.7 Instrument Operator's Name: Elijah Frane-High Prairie Survey

If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

Sec: Twp: Rng: Sec: Twp: Rng:

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply)

☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place:

Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

W/2 Section 23-3S-53W

Total Acres in Described Lease: 320 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 184 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 2580 Feet

Building Unit: 2580 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 1740 Feet

Above Ground Utility: 5280 Feet

Railroad: 5280 Feet

Property Line: 184 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 5280 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary _____ Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
J SAND	JSND			

DRILLING PROGRAM

Proposed Total Measured Depth: 5000 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 1799 Feet (Including plugged wells)

Will a closed-loop drilling system be used? No

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☐ Double Ram ☐ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: ONSITE Cuttings Disposal Method: Drilling pit

Other Disposal Description:

Water based Bentonitic drilling fluids, except deminimis amounts will be removed from the drilling pit and disposed in accordance with the 900 series rules.

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	11	8+5/8	23	0	350	150	350	0
1ST	7+7/8	5+1/2	15.5	0	5000	200	5000	3500

☒ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: MICHAEL J. REILLY

Title: PRESIDENT Date: 8/31/2015 Email: PBREWER@GMOCKS.COM

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 11/5/2015

Expiration Date: 11/04/2017

API NUMBER

05 121 11058 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type**Description**

- | | |
|--|---|
| | <ol style="list-style-type: none">1) Provide 48 hour notice prior to spud via electronic Form 42.2) Provide cement coverage from TD to a minimum of 200' above J-Sand. Verify coverage with cement bond log.3) If dry hole, set 40 sks cement at top of J-Sand, 50 sks cement ½ out, ½ in surface casing, 15 sks cement top of surface casing, cut 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole. |
|--|---|

Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Drilling/Completion Operations	<p>BMP Plan Grand Mesa Operating, Co. 1700 N Waterfront Pkwy, Bldg 600 Wichita, KS 67206 P - 316-265-3000 F - 316-265-3455</p> <p>Certification of Discharge under CDPHE COR-0300000 Storm water discharges associated with certification number COR030094</p> <p>Prior to construction, perimeter controls will be installed utilizing cutting from the clearing operations. Once the well pad has been constructed a variety of BMP's shall be utilized for the site specific conditions. BMP's to be utilized may include, but are not limited to:</p> <ul style="list-style-type: none">-Dirt berms-Erosion control blankets-Straw bale barrier-Straw wattle-Check dams-Culvert/Culvert Protection-Silt Fence-Surface roughening/Surface rip <p>Drill pits will be filled and reclaimed within 3 months weather permitting. Topsoil will be separated and spread on drill site as final operation. Storm Water Management Plan (SWMP) is on file in Grand Mesa Operating, Co office. Spill Prevention, Control and Countermeasure Plan is on file in Grand Mesa Operating, Co. office.</p>
2	Drilling/Completion Operations	<p>Per Rule 317.p -- Open-hole Resistivity Log with Gamma Ray Log will be run from TD into the surface casing. A Cement Bond Log with Gamma-Ray will be run on production casing, or on intermediate casing if a production liner is run. The Form 5, Completion Report, will list all logs run and have those logs attached.</p>

Total: 2 comment(s)

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
901329	OTHER
1897990	SURFACE CASING CHECK
400852326	FORM 2 SUBMITTED
400873343	UNIT CONFIGURATION MAP
400873346	30 DAY NOTICE LETTER
400873351	CONSULT NOTICE
400873410	WELL LOCATION PLAT

Total Attach: 7 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Per Operator request, changed the distance to the nearest Public Road to 1740 feet. Per Operator and Washington County, the road located 184 feet to the west of the well is a private road.	11/4/2015 10:22:52 AM
Final Review	Distance from well to road is less than 200' as required by Rule 603.a. with no variance request indicated. Reactivated Final Review Task.	10/29/2015 10:10:02 PM
Permit	Final Review Completed. No LGD or public comment received.	10/6/2015 4:12:49 PM
Permit	Operator submitted voluntary pooling documentation, which has been uploaded to the attachments as "OTHER."	10/2/2015 8:36:10 AM
Permit	Need voluntary pooling documentation. Corrected distance to nearest building to match distance to nearest building unit. Removed distance from completed portion of wellbore to nearest unit boundary, as no unit exists.	10/1/2015 3:09:09 PM
Permit	Pass completeness	9/3/2015 10:51:49 AM

Total: 6 comment(s)