

## US ROCKIES REGION

## Anadarko Daily Summary Report

Well: HSR-STREED 10-13

Project:COLORADO-WELD-NAD83-UTM13

Site:HSR-STREED 10-13

Rig name no.:ENSIGN 320/320

Event: WELL WORK EXPENSE

Start date: 10/19/2015

End date:

Spud date: 12/15/1996

Active datum: RKB @4,793.99usft (above Mean Sea Level)

UWI: NW/SE/0/3/N/67/W/13/0/0/6/PM/S/2,064.00/E/0/0/0/0

Report no.	Report date	MD (usft)	24 hr summary
1	10/16/2015		MIRU SUMMIT SLICKLINE, FISH PLUNGER & BUMPER SPRING, TAG S.N. @ 7291' & TD @ 7324', <b>GYRO WELL FROM SURFACE TO 7200'</b> , RDMO SUMMIT SLICKLINE
2	10/19/2015		MIRU ENSIGN #320, KILL WELL, NU BOP, RU PICK TESTERS EMI UNIT, TOO H w/ 232JTS OF 2.375" 4.7# J-55 TBG, 8JTS GOOD(YELLOW), 224JTS BAD(RED), RD PICK TESTERS EMI UNIT, SWI, DRAIN UP, SDFN
3	10/20/2015		PU THUNDERBIRD 4-1/2" RBP, TIH, SET @ 6970', TEST CSG TO 1000PSI - HELD 15MIN, DUMP 2SX OF SAND ONTOP OF RBP @ 6970', TOO H, RD FLOOR & TONGS, ND BOP, UNLAND 4-1/2' CSG, NU DUAL ENTRY FLANGE & EQUIPMENT, NU BOP, RU 1.66" TBG EQUIPMENT, SWI, DRAIN UP, SDFN
4	10/21/2015		TIH w/ 1.66" 2.33# J-55 10RD IJ TBG INSIDE ANNULUS, PUMP SWEEP w/ ALCOMER 74-L @ 990', TIH, PUMP SWEEP w/ ALCOMER 74-L @ 3100', TIH, EOT @ 4730', PUMP FINAL SWEEP w/ ALCOMER 74-L, CIRCULATE HOLE UNTIL NO GAS IS PRESENT, SWI, DRAIN UP, SDFN
5	10/22/2015		EOT @ 4730', CIRCULATE HOLE, PUMP 40BBLs 10# MUD, PUH, EOT @ 4475', RU SANJEL CEMENTERS, <b>PUMP 150SX OF 14.6# 1.12 YIELD CLASS G CEMENT</b> , PUH, EOT @ 1085, <b>PUMP 145SX OF 14.8# 1.33 YIELD TYPE 3 CEMENT</b> , TOO H, ND DUAL ENTRY FLANGE, NU NEW 5K WELLHEAD, SWI,SDFN
6	10/23/2015		RU WARRIOR WIRELINE, <b>LOG WELL FROM 6700' TO SURFACE</b> , RD WIRELINE, TIH, ROLL SAND OFF OF RBP @ 6970', RELEASE RBP & TOO H, TIH 2.375" NOTCHED COLLAR, 2.375" XN NIPPE ON 2.375" TBG, LAND TBG @ 7298'KB, BROACH TBG, TORQUE & TEST TBG HEAD, RDMO ENSIGN #320