

FORM  
5Rev  
09/14

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400913531

Date Received:

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 47120

Contact Name: Kayla Hesseltine

Name of Operator: KERR MCGEE OIL &amp; GAS ONSHORE LP

Phone: (720) 929-6552

Address: P O BOX 173779

Fax:

City: DENVER State: CO Zip: 80217-

API Number 05-123-41557-00

County: WELD

Well Name: CARTER

Well Number: 13N-33HZ

Location: QtrQtr: NENW Section: 33 Township: 2N Range: 66W Meridian: 6

Footage at surface: Distance: 825 feet Direction: FNL Distance: 1380 feet Direction: FWL

As Drilled Latitude: 40.099579 As Drilled Longitude: -104.786694

## GPS Data:

Date of Measurement: 07/27/2015 PDOP Reading: 1.0 GPS Instrument Operator's Name: Sergio Del Carmen

\*\* If directional footage at Top of Prod. Zone Dist.: 327 feet. Direction: FNL Dist.: 1051 feet. Direction: FWL

Sec: 33 Twp: 2N Rng: 66W

\*\* If directional footage at Bottom Hole Dist.: 47 feet. Direction: FSL Dist.: 1026 feet. Direction: FWL

Sec: 33 Twp: 2N Rng: 66W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 07/18/2015 Date TD: 09/18/2015 Date Casing Set or D&amp;A: 09/19/2015

Rig Release Date: 09/29/2015 Per Rule 308A.b.

## Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 12726 TVD\*\* 7337 Plug Back Total Depth MD 12623 TVD\*\* 7338

Elevations GR 4960 KB 4976 Digital Copies of ALL Logs must be Attached per Rule 308A ☐

## List Electric Logs Run:

CBL, GR

## CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42.1	0	56	36	0	56	VISU
SURF	13+1/2	9+5/8	36	0	1,866	750	0	1,866	VISU
1ST LINER	7+7/8	5+1/2	17	0	12,716	1,440	28	12,716	CBL

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

## FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	4,589				
SHARON SPRINGS	7,336				
NIOBRARA	7,414				

Comment:

Due to anti-collision needs and the variability of directional drilling, our as-drilled BHL could be different than the permitted.

This well has two different weights of surface casing. From 0-1217', the casing weight is 47 lbs/ft. From 1217-1866' the casing weight is 36 lbs/ft.

Per Rule 371.p Exception, compensated neutron logs have been run on Carter 14C-33HZ (05-123-41551)

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Kayla Hesseltine

Title: Regulatory Specialist

Date: \_\_\_\_\_

Email: kayla.hesseltine@anadarko.com

## Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400926071	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400913541	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400913537	LAS-MEASUREMENT/LOGGING WHILE DRILLING	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400913538	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400913539	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400933067	PDF-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

### General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)