

Document Number:  
400908006

Date Received:

**DRILLING COMPLETION REPORT**

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type  Final completion  Preliminary completion

OGCC Operator Number: 47120 Contact Name: Kayla Hesseltine  
 Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6552  
 Address: P O BOX 173779 Fax: \_\_\_\_\_  
 City: DENVER State: CO Zip: 80217-

API Number 05-123-41552-00 County: WELD  
 Well Name: CARTER Well Number: 14N-33HZ  
 Location: QtrQtr: NENW Section: 33 Township: 2N Range: 66W Meridian: 6  
 Footage at surface: Distance: 825 feet Direction: FNL Distance: 1470 feet Direction: FWL  
 As Drilled Latitude: 40.099579 As Drilled Longitude: -104.786375

GPS Data:  
 Date of Measurement: 07/27/2015 PDOP Reading: 1.0 GPS Instrument Operator's Name: Sergio Del Carmen

\*\* If directional footage at Top of Prod. Zone Dist.: 475 feet. Direction: FNL Dist.: 1979 feet. Direction: FWL  
 Sec: 33 Twp: 2N Rng: 66W  
 \*\* If directional footage at Bottom Hole Dist.: 51 feet. Direction: FSL Dist.: 2083 feet. Direction: FWL  
 Sec: 33 Twp: 2N Rng: 66W

Field Name: WATTENBERG Field Number: 90750  
 Federal, Indian or State Lease Number: \_\_\_\_\_

Spud Date: (when the 1st bit hit the dirt) 07/20/2015 Date TD: 09/05/2015 Date Casing Set or D&A: 09/06/2015  
 Rig Release Date: 09/29/2015 Per Rule 308A.b.

Well Classification:  
 Dry  Oil  Gas/Coalbed  Disposal  Stratigraphic  Enhanced Recovery  Storage  Observation

Total Depth MD 12709 TVD\*\* 7330 Plug Back Total Depth MD 12605 TVD\*\* 7332  
 Elevations GR 4960 KB 4976 **Digital Copies of ALL Logs must be Attached per Rule 308A**

List Electric Logs Run:  
CBL, GR

**CASING, LINER AND CEMENT**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42.1	0	56	36	0	56	VISU
SURF	13+1/2	9+5/8	36	0	1,851	743	0	1,851	VISU
1ST	7+7/8	5+1/2	17	0	12,699	1,440	50	12,699	CBL

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

## FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	4,628				
SHARON SPRINGS	7,384				
NIOBRARA	7,466				

Comment:

Due to anti-collision needs and the variability of directional drilling, our as-drilled BHL could be different than the permitted. Per Rule 371.p Exception, compensated neutron logs have been run on Carter 14C-33HZ (05-123-41551)

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Kayla Hesseltine

Title: Regulatory Specialist Date: \_\_\_\_\_ Email: kayla.hesseltine@anadarko.com

### Attachment Check List

Att Doc Num	Document Name	attached ?	
<b>Attachment Checklist</b>			
400908016	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400908014	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<b>Other Attachments</b>			
400908008	LAS-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400908009	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400908011	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400933063	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

## General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)