

WELLBORE DIAGRAM
NGL Water Solutions DJ LLC
NGL C5A
 NESW Sec 29-T2N-R64W
 Weld County , CO
 API unassigned

Planned

12/4/2014

PAG

TOPS

 All listed in MD

K.B.= 4959
 G.L.= 4937
 22

Niobrara - 6892'

Codell - 7147'

J Sand - 7583'

Lyons - 8782'

L. Satanka- 8910'

Wolfcamp- 9180'

Amazon - 9230'

Council Grove - 9290'

Admire - 9440'

Virgil - 9540'

Missouri - 9730'

Fountain - 9875'

Des Moines - 10075'

Atoka - 10333'

Morrow - 10613'

TD - 10,640'

9-5/8", 36# J-55 ST&C CSG Set @ 1000' (12-1/4" O.H.)
 Cmt'd w/ 281 sx total

DV Tool @ 7407'
 Cmt'd w/ 622 sx lead, 139 sx tail - TOTAL 761 sks

4-1/2" tbg
 EOT & Packer @ 8632'

PBR & TOL @ 8682'
 7" 26# N-80 LT&C CSG Set @ 8782' (8-3/4" O.H.)
 Cmt'd w/ 122 sx (1st stage)

Slotted Pipe Liner slotted with 2" by 0.040" slots on 6" centers

4-1/2" 11.6# N-80 LT&C Slotted LNR (TOL @ 8682', EOL @ 10,640')
 (6-1/8" O.H.)

MD = 10,640'