

FORM
5Rev
09/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400944025

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 10439

Contact Name: Madelon Raney

Name of Operator: CARRIZO NIOBRARA LLC

Phone: (713) 358-6218

Address: 500 DALLAS STREET #2300

Fax:

City: HOUSTON

State: TX

Zip: 77002

API Number 05-123-36869-00

County: WELD

Well Name: Nelson

Well Number: 4-17-9-60

Location: QtrQtr: SESW Section: 17 Township: 9N Range: 60W Meridian: 6

Footage at surface: Distance: 291 feet Direction: FSL Distance: 1595 feet Direction: FWL

As Drilled Latitude: 40.743000 As Drilled Longitude: -104.121240

GPS Data:

Date of Measurement: 10/31/2013 PDOP Reading: 2.8 GPS Instrument Operator's Name: Marc Woodard

** If directional footage at Top of Prod. Zone Dist.: 324 feet. Direction: FSL Dist.: 1955 feet. Direction: FWL

Sec: 17 Twp: 9N Rng: 60W

** If directional footage at Bottom Hole Dist.: 650 feet. Direction: FNL Dist.: 1942 feet. Direction: FWL

Sec: 17 Twp: 9N Rng: 60W

Field Name: DJ HORIZONTAL NIOBRARA

Field Number: 16950

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 04/14/2013 Date TD: 05/08/2013 Date Casing Set or D&A: 05/02/2013

Rig Release Date: 05/10/2013 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 10754 TVD** 6452 Plug Back Total Depth MD 10754 TVD** 6452

Elevations GR 4992 KB 5009

Digital Copies of ALL Logs must be Attached per Rule 308A ☐

List Electric Logs Run:

MWD LOG AND CBL LOG

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	30	16	36.9	0	60	8	0	60	VISU
SURF	12+1/4	9+5/8	36	0	1,416	557	0	1,416	VISU
1ST	8+3/4	7	23	0	6,441	559	1,410	6,441	CBL
1ST LINER	6+1/8	4+1/2	11.6	5798	10,734				

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PIERRE		6,335	NO	NO	FORMATIONS NOT RECORDED IN THIS WELL
SHARON SPRINGS	6,260	6,335	NO	NO	
NIOBRARA	6,335	10,754	NO	NO	

Comment:

OPEN HOLE LOG NOT RAN. COGCC LOG SUBMITTAL POLICY NOT RELEASED AT THE TIME OF DRILLING THIS WELL.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Madelon RaneyTitle: Regulatory Compl. Analyst Date: _____ Email: madelon.raney@crzo.net

Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
400944039	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
400944038	Directional Survey **	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
400944035	LAS-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
400944036	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
400944037	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
400944041	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)