

US ROCKIES REGION			
Anadarko Daily Summary Report			
Well: FT ST VRAIN 17			
Project:COLORADO-WELD-NAD83-UTM13		Site:FT ST VRAIN 17	Rig name no.:BASIC 1524/1524
Event: WELL WORK EXPENSE		Start date: 11/2/2015	End date: Spud date: 9/12/1982
Active datum: RKB @4,763.99usft (above Mean Sea Level)		UWI: 0/4/N/67/W/34/0/SESE/6/0/0/0/0/0/0	
Report no.	Report date	MD (usft)	24 hr summary
1	11/02/2015		SLICKLINE TAG @7088'KB. MIRU BASIC 1524.BLOW WELL DOWN. KILL. ND WH, NU BOP'S. MIRU EMI TOO H W/223JNT'S 2.375 GOOD. TIH SET RBP@6698' W/212JNT'S. CIRCULATE GAS OUT OF WELL.PSI TEST TO 1000#. SPOT 2SX SAND ON RBP. TOO H LD. SWI SDFN.
2	11/03/2015		ND UNLAND CSG@70K,NU. PU MULE SHOE TIH(ANNULUS) CIRCULATING IN SPOT'S TO EOT@5095' W/156JNT'S 1.25 TBG. BREAK CIRCULATION, MAKE SWEEP OF ALCOMER 74L CIRCULATE CONDITION HOLE. PUH EOT@4933' W/151 JNT'S 1.25 TBG SWI SDFN.
3	11/04/2015		TIH 5JNT'S EOT@5095' W/215JNT'S 1.25.CIRCULATE.SPOT20BBL'S 10# MUD. PUH EOT@4641'.MIRU SANJEL PUMP 355SX 1:1 G CEMENTSHSX PLUG. PUH EOT@1013' PUMP 200SX TYPE III CEMENT FOXHILLS PLUG. TOO H 1.25 TBG. ND RELAND 4.5"CSG@60K.NU SWI SDFN.
4	11/05/2015		NU.MIRU FMC WL RIH LOG 6276'-11' SHSX TOC@3720'-BOC@4752',&FOXHILLS TOC@434'-BOC@1100'.PSI TEST TO 1000#.GOOD TEST.TIH TAG SAND ON RBP @6698' W/212JNT'S.CO SAND RETRIEVE/RELEASE RBP@6698' W/212JNT'S.TOO H LD.PU NC,XN NIPPLE TIH TO 6692' W/212JNT'S SWI,SDFN
5	11/06/2015		FINISH TIH TAG FILL@7088'KB W/225JNT'S.BREAK CIRCULATION W/60BBL'S CO TO 7131'KB W/226JNT'S.HIT HARD SPOT.CIRCULATE HOLE CLEAN.PUH LAND TBG@ 7050' KB W/223JNT'S 2.375 TBG. BROACH TBG.ND,NU WH.TORQUE & PSI TEST WH TO 5000#.RDMO BASIC 1524.SWI SDFN.

COMMENTS:

11/06/15 - WELL HAS NEW FLANGE VALVE TOP & 8" XXH NIPPLE'S, & 5K BALLONS