

US ROCKIES REGION			
Anadarko Daily Summary Report			
Well: FT ST VRAIN 20			
Project:COLORADO-WELD-NAD83-UTM13	Site:FT ST VRAIN 20		Rig name no.:LEED 724/724
Event: ABANDONMENT	Start date: 11/9/2015	End date: 11/23/2015	Spud date: 4/21/1992
Active datum: RKB @4,771.99usft (above Mean Sea Level)		UWI: 0/3/N/67/W/9/0/NWSE/6/0/0/0/0/0/0/0	
Report no.	Report date	MD (usft)	24 hr summary
1	11/05/2015		MIRU CORE TECH S/L. FISH PLUNGER/SV. TAG FILL @ 7152 KB. RUN PRESSURE BOMB FROM 7050 TO SURFACE. MAKING GRADIENT STOP EVERY 1000'. RDMO CORE TECH S/L
2	11/09/2015		MIRU LEED 724. RU PUMP. VAC/200/SURF 40. BD WELL TO WORK TANK. KILL W/20 BW-BIO. ND 3K WH. NUBOP. TOO H W/224 JTS(7051.95). RU WARRIOR W/L. RUN G. RING TO 6800. SET CIBP @ 6770. RD WARRIOR W/L. SWI SDFN.
3	11/10/2015		WELL DEAD/SURF 40. RU HS T. TIH W/214 JTS HYDROTESTING TO 3000. RD HS T. CIRC GAS OUT. TEST CSG/CIBP TO 1000 FOR 15 MIN. GOOD TEST. RU SANJEL. PUMP 25 SX THERMAL 35 CMT BAL PLUG @ 6765. DISP W/22 BW. RD SANJEL. LD 14 JTS CIRC TBG CLEAN @ 6200. SEE REMARKS:
4	11/12/2015		THUNDERBIRD 4-1/2" CIRC SET @ 3740', RU SANJEL CEMENTERS. PUMP 230SX OF 15.8# 1.15 YIELD CLASS G CEMENT, TOO H, RU WARRIOR WIRELINE, RIH w/ 4-1/2" JET CUTTER, CUT CSG @ 840', ND BOP, UNLAND CSG, NU SPOOL & BOP, TOO H, LD CSG, TIH, EOT @ 945', SWI, SDFN
5	11/13/2015		0/0 SURF 0. OPEN SURF. NO FLUID. CIRC WELL WHILE RIGGING UP SANJEL. PUMP 5 BW, 10 BBLS SAPP, 5 BW SPACER. 250 SX(59.2 BBLS), TYPE III CMT @ 14.8 PPG & 1.33 CF/SK. DISP W/ 2 BW. RD SANJEL. LD 27 JTS. CIRC TBG CLEAN W/3 JTS IN @ 96'. LD 3 JTS. SWI SDFN.
6	11/16/2015		PU TAG JTS. TAG TOC W/4.5 JTS @ 140'. LD TAG JTS. NDBOP & ADAPTOR FLANGE. RU WARRIOR W/L. RIH W/8-5/8 CIBP. SET @ 80'. RD WARRIOR W/L. TEST CIBP TO 1000 HELD 15 MIN. GOOD TEST. RD PUMP. RDMO 724
7	11/23/2015		Exposed surface casing. Cut casing 6' below GL. Tagged @ 71'. Filled casing stub with 39 bags 5000 psi cement. Capped casing with a metal plate containing well info. Backfilled.
8	11/23/2015		TIME : 0.479166666666667, ROUTE : N21, WINS: 75652, PROJECT TYPE: P&A, PROD: NB/CD, BATT#: 34003227, GATHERER: DCP, STATION: 232820, LINE : NA, COMMENTS: P&A'd OFFLINE.
REMARKS:			

11/10/15 - LD TBG. STD BACK 59 STDS. RU WARRIOR W/L. RIH W/3-1/8 PERFGUN. SHOT SQUEEZE HOLES @ 4120 & 3710 W/3 SPF TOTAL 9 HOLES. RD W/L. PU T.BIRD CIRC. TIH W/119 JTS. SET CIRC @ 3740. SWI SDFN.

11/12/15 - BRADENHEAD PRESSURE @ 40PSI w/ FLUID(WATER) - RIG UP HOSE ON SURFACE CSG VALVE, OPEN UP & LET FLUID BLEED OFF TO OUR TANK, LEAVE VALVE OPEN ALL DAY AND SHUT IN AT THE END OF THE DAY