

APPLICATION FOR PERMIT TO:

Drill Deepen Re-enter Recomplete and Operate

TYPE OF WELL OIL <input checked="" type="checkbox"/> GAS <input type="checkbox"/> COALBED <input type="checkbox"/> OTHER <u>Lateral Wellbore</u>	Refiling <input type="checkbox"/>
ZONE TYPE SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONES <input type="checkbox"/> COMMINGLE ZONES <input type="checkbox"/>	Sidetrack <input type="checkbox"/>

Date Received:
08/28/2015

Well Name: Grande 4-65 20-19 Well Number: 1DH

Name of Operator: BURLINGTON RESOURCES OIL & GAS LP COGCC Operator Number: 26580

Address: PO BOX 4289

City: FARMINGTON State: NM Zip: 87499

Contact Name: Ali Savage Phone: (281)2065359 Fax: ()

Email: ali.savage@conocophillips.com

RECLAMATION FINANCIAL ASSURANCE
Plugging and Abandonment Bond Surety ID: 19920030

WELL LOCATION INFORMATION

QtrQtr: NENE Sec: 20 Twp: 4S Rng: 65W Meridian: 6

Latitude: 39.695006 Longitude: -104.680722

Footage at Surface: 560 feet FNL 650 feet FEL

Field Name: WILDCAT Field Number: 99999

Ground Elevation: 5657 County: ARAPAHOE

GPS Data:
Date of Measurement: 04/23/2015 PDOP Reading: 1.2 Instrument Operator's Name: Dallas Nielsen

If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone:	FNL/FSL	FEL/FWL	Bottom Hole:	FNL/FSL	FEL/FWL
<u>1216</u>	<u>FNL</u>	<u>1223</u>	<u>1216</u>	<u>FNL</u>	<u>325</u>
Sec: <u>20</u>	Twp: <u>4S</u>	Rng: <u>65W</u>	Sec: <u>19</u>	Twp: <u>4S</u>	Rng: <u>65W</u>

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: Fee State Federal Indian

The Surface Owner is: is the mineral owner beneath the location.
(check all that apply) is committed to an Oil and Gas Lease.
 has signed the Oil and Gas Lease.
 is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: Fee State Federal Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: Surface Surety ID: _____

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Sec 20, 19 4S 65W ALL; except an 8.85 acre parcel of land in the NW/4NE/4 of Section 20, T4S, R65W.

Total Acres in Described Lease: 1271 Described Mineral Lease is: Fee State Federal Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 460 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 1299 Feet

Building Unit: 4930 Feet

High Occupancy Building Unit: 5280 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 633 Feet

Above Ground Utility: 615 Feet

Railroad: 5280 Feet

Property Line: 560 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: Buffer Zone
 Exception Zone
 Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 3156 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 460 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	535-686	1280	Sec 19 & 20 All

DRILLING PROGRAM

Proposed Total Measured Depth: 17382 Feet

Distance from proposed wellbore to nearest existing or permitted wellbore belonging to another operator:

3156 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H2S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H2S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: Annular Preventor Double Ram Rotating Head None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Oil based mud will not be used when drilling the surface section.

Beneficial reuse or land application plan submitted?

Reuse Facility ID: or Document Number:

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	39.7	0	100	50	100	0
SURF	13+1/2	9+5/8	36	0	2114	670	2114	0
1ST	8+3/4	5+1/2	23	0	17382	2210	17382	2114

Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- Rule 318A.a. Exception Location (GWA Windows).
- Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number

OTHER LOCATION EXCEPTIONS

Check all that apply:

- Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Ali Savage

Title: Regulatory Specialist Date: 8/28/2015 Email: ali.savage@conocophillips.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: *Matthew Lee* Director of COGCC Date: 12/6/2015

Expiration Date: 12/05/2017

API NUMBER

05 005 07252 01

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	PILOT HOLE 1) Submit Form 42 spud notice electronically to COGCC 48 hours prior to MIRU. FOR LATERAL 2) Comply with Rule 317.j. and provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
--	---

Best Management Practices

No	<u>BMP/COA Type</u>	<u>Description</u>
1	General Housekeeping	All surface trash, debris, scrap or discarded material will be removed daily or weekly as necessary and in a legal manner.
2	Storm Water/Erosion Control	Storm Water Management Plan (SWMP) will be in place to address construction, drilling and operations associated with oil and gas development through the state of Colorado in accordance with CDPHE General Permit Rules. BMP's will vary according to location and will remain in place until the pad reaches final reclamation.
3	Material Handling and Spill Prevention	Spill prevention control and countermeasure plan is in place to address construction, drilling and operations associated with oil and gas development throughout the state of Colorado in accordance with CFR 112.
4	Drilling/Completion Operations	Open-hole Resistivity Log with Gamma Ray Log will be run from the kick-off point into the surface casing. A Cement Bond Log with Gamma-Ray will be run on production casing, or on intermediate casing if a production liner is run. The horizontal portion of the wellbore will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, will list all logs run and have those logs attached.
5	Drilling/Completion Operations	Preferred Option: It is the intent of the County that operators utilize closed-loop or modified closed-loop systems for drilling and completion operations in order to minimize or eliminate the need for earthen pits; however, notwithstanding the foregoing, where appropriate, and subject to prior County approval, the County generally supports: 1) the use of unlined drilling pits when bentonite or a similar clay additive is used during the drilling process, and 2) the use of lined single- or multi-well water storage pits in order to minimize the transport of water and promote recycling, subject to the requirements set forth in this subsection. Permitted modified closed-loop systems include oil and gas wells where air or fresh water is used to drill through the surface casing interval, defined as fifty (50) feet below the depth of the deepest aquifer, and a closed loop system is used for the remainder of the drilling and/or completion or recompletion procedures. Multi-well pits are defined as lined, engineered pits, constructed over an engineered base, with construction or liner specifications meeting or exceeding Commission pit lining rules, that will serve the functions of drilling, completion, and/or flowback pits for more than one well.

Total: 5 comment(s)

Applicable Policies and Notices to Operators

Policy
Notice Concerning Operating Requirements for Wildlife Protection. http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400846633	FORM 2 SUBMITTED
400849509	WELL LOCATION PLAT
400891190	DEVIATED DRILLING PLAN
400891198	DIRECTIONAL DATA

Total Attach: 4 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed. No LGD or public comment received.	12/2/2015 11:33:10 AM
Permit	Added spacing unit configuration per the operator.	12/2/2015 11:21:11 AM
Engineer	Offset wells evaluated	10/21/2015 3:33:23 PM
Permit	Corrected lease description per the operator. Added distance to nearest lease line per the operator.	9/24/2015 1:24:57 PM
Permit	Requested lease clarification.	9/24/2015 11:17:04 AM
Permit	Pass completeness	8/31/2015 2:36:05 PM

Total: 6 comment(s)