

FORM
5A

Rev
06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400948276

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120

2. Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

3. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-

4. Contact Name: ILA BEALE

Phone: (720) 929-6408

Fax:

Email: ila.beale@anadarko.com

5. API Number 05-069-06478-00

7. Well Name: ENCORE

8. Location: QtrQtr: NWNW Section: 12 Township: 5N Range: 68W Meridian: 6

9. Field Name: WATTENBERG Field Code: 90750

6. County: LARIMER

Well Number: 8C-12HZ

Completed Interval

FORMATION: CODELL Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 11/04/2015 End Date: 11/14/2015 Date of First Production this formation: 11/23/2015
Perforations Top: 8034 Bottom: 13820 No. Holes: 452 Hole size: 0.46

Provide a brief summary of the formation treatment:

Open Hole: ☐

"PERF AND FRAC FROM 8034-13,820.
100,217 BBL SLICKWATER, 5,927 BBL WATER, - 106,144 BBL TOTAL FLUID
3,152,540# 40/70 GENOA/SAND HILLS, - 3,152,540# TOTAL SAND."

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 106144

Max pressure during treatment (psi): 6783

Total gas used in treatment (mcf): 0

Fluid density at initial fracture (lbs/gal): 8.30

Type of gas used in treatment: _____

Min frac gradient (psi/ft): 0.81

Total acid used in treatment (bbl): 0

Number of staged intervals: 19

Recycled water used in treatment (bbl): 0

Flowback volume recovered (bbl): 1364

Fresh water used in treatment (bbl): 106144

Disposition method for flowback: DISPOSAL

Total proppant used (lbs): 3152540

Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized: _____

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 12/04/2015 Hours: 24 Bbl oil: 192 Mcf Gas: 195 Bbl H2O: 1
Calculated 24 hour rate: Bbl oil: 192 Mcf Gas: 195 Bbl H2O: 1 GOR: 1016
Test Method: FLOWING Casing PSI: 1400 Tubing PSI: _____ Choke Size: 28/64
Gas Disposition: SOLD Gas Type: WET Btu Gas: 1366 API Gravity Oil: 45
Tubing Size: _____ Tubing Setting Depth: _____ Tbg setting date: _____ Packer Depth: _____

Reason for Non-Production: _____

Date formation Abandoned: _____ Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt _____

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: ILA BEALE

Title: STAFF REG. SPECIALIST Date: _____ Email: ila.beale@anadarko.com

Attachment Check List

Att Doc Num Name

Total Attach: 0 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)