

FORM

2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

400889914

(SUBMITTED)

Date Received:

APPLICATION FOR PERMIT TO:

☒ Drill
 ☐ Deepen
 ☐ Re-enter
 ☐ Recomplete and Operate
TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER _____Refilling ☐ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐Sidetrack ☐

Well Name: Dittmer KE

Well Number: 20-022HC

Name of Operator: GREAT WESTERN OPERATING COMPANY LLC

COGCC Operator Number: 10110

Address: 1801 BROADWAY #500

City: DENVER

State: CO

Zip: 80202

Contact Name: Allison Linz

Phone: (303)398-0355

Fax: ()

Email: regulatorypermitting@gwogco.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20090080

WELL LOCATION INFORMATION

QtrQtr: NENW Sec: 32 Twp: 1N Rng: 66W Meridian: 6

Latitude: 40.011917

Longitude: -104.802528

Footage at Surface: 1103 feet FNL/FSL FNL 2199 feet FEL/FWL FWL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 4966

County: WELD

GPS Data:

Date of Measurement: 04/03/2015 PDOP Reading: 1.3 Instrument Operator's Name: Dallas Nielsen

If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**
 Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FNL/FWL
 460 FSL 470 FWL 470 FNL 470 FWL
 Sec: 29 Twp: 1N Rng: 66W Sec: 20 Twp: 1N Rng: 66W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ IndianThe Surface Owner is: ☐ is the mineral owner beneath the location.

(check all that apply)

☐ is committed to an Oil and Gas Lease.☐ has signed the Oil and Gas Lease.☐ is the applicant.The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place:

Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

N/2NW sec 20 . Irregular Lease description please see attached map.

Total Acres in Described Lease: 80 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 936 Feet
Building Unit: 936 Feet
High Occupancy Building Unit: 3094 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 1092 Feet
Above Ground Utility: 898 Feet
Railroad: 2583 Feet
Property Line: 220 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 08/21/2015

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 554 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 460 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

Sec 20: W2 ; Sec 29: W2

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL		640	GWA

DRILLING PROGRAM

Proposed Total Measured Depth: 18083 Feet

Distance from proposed wellbore to nearest existing or permitted wellbore belonging to another operator:

740 Feet (Including plugged wells)

Will a closed-loop drilling system be used? No

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☐ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	42	0	80	121	80	0
SURF	13+1/2	9+5/8	36	0	2100	874	2100	0
1ST	7+7/8	5+1/2	17	0	18083	1738	18083	0

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☒ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments Please refer to language in SUA for twinning and windows waivers.

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? _____ Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Allison Linz

Title: Regulatory Date: _____ Email: regulatorypermitting@gwogco.c

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Expiration Date: _____

API NUMBER

05

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

Best Management Practices

No	BMP/COA Type	Description
1	General Housekeeping	<p>Housekeeping</p> <p>General housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with storm water runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup will consist of patrolling the roadways, access areas, and other work areas to pick up trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly and promptly.</p>
2	Drilling/Completion Operations	<p>Bradenhead Monitoring</p> <p>GWOC will comply with the "COGCC Policy for Bradenhead Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area", dated May 29, 2012</p>
3	Drilling/Completion Operations	<p>Multi Well Open Hole Logging</p> <p>One of the first wells drilled on the pad will be logged with open-hole Resistivity and Gamma Ray Log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing id production liner is run) into the surface casing. The horizontal portion of every well will be logging with a measure-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open hole logs shall clearly state "No open-hole logs were run" and shall clearly identify (by API#, well name and number) the well in which open-hole logs were run.</p>
4	Drilling/Completion Operations	<p>Stimulation Setback (Rule 317.r and 317.s)</p> <p>Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment.</p>
5	Drilling/Completion Operations	<p>Odors and Light Pollution Mitigation</p> <p>During the drilling phase, Great Western plans to construct sound/visual walls that will be placed along the North, East, and South edges of the pad. This will also assist to block out any lighting from nearby occupied structures. Where possible, drilling rig and completion equipment engine exhaust will be directed away from occupied buildings. Sealed tanks with pressure relief valves and emissions controls will also be utilized during the production phase.</p>
6	Drilling/Completion Operations	<p>Identification of P&A wells (Rule 604.c.(2)U)</p> <p>GWOC shall identify the location of the P&A wellbore with a permanent monument as specified in Rule 319.a.(5). The operator shall also inscribe or imbed the well number and date of plugging upon the permanent monument. P&A wellbores shall be cutoff well below ground surface in agricultural areas to provide for landowners to safely farm the reclaimed well area.</p>

7	Drilling/Completion Operations	<p>Identification of P&A wells (Rule 604.c.(2)U)</p> <p>GWOC shall identify the location of the P&A wellbore with a permanent monument as specified in Rule 319.a.(5). The operator shall also inscribe or imbed the well number and date of plugging upon the permanent monument. P&A wellbores shall be cutoff well below ground surface in agricultural areas to provide for landowners to safely farm the reclaimed well area.</p>
8	Drilling/Completion Operations	<p>Odors and Light Pollution Mitigation</p> <p>Where possible, drilling rig and completion equipment engine exhaust will be directed away from occupied buildings to assist in mitigating potential odors. Light sources will be directed downwards, and away from occupied structures where possible. While GWOC does not anticipate any mitigation measures will be necessary for odors, sealed tanks with pressure relief valves and emissions controls will be utilized for the production phase. Once the drilling and completion rigs leave the site, there will be no permanently installed lighting on site.</p>
9	Drilling/Completion Operations	<p>Drill stem tests (Rule 604.c.(2)L)</p> <p>Conventional drill stem tests will not be conducted on DJ Basin horizontal wells currently being executed or planned by GWOC. If plans change in the future a well specific drill stem testing plan will be prepared for that particular well. Note that GWOC may elect to use one of several available wireline deployed tools for the purpose of measuring downhole formation pressures and/or collecting downhole fluid samples from the target formation(s) of a particular well.</p>

Total: 9 comment(s)

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400889951	OffsetWellEvaluations Data
400946042	WELL LOCATION PLAT
400946043	MINERAL LEASE MAP
400946045	SURFACE AGRMT/SURETY
400946047	EXCEPTION LOC REQUEST
400946053	30 DAY NOTICE LETTER
400946055	DEVIATED DRILLING PLAN
400946056	DIRECTIONAL DATA

Total Attach: 8 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)