

US ROCKIES REGION			
Anadarko Daily Summary Report			
Well: SAWDEY GLADYS 1			
Project:COLORADO-WELD-NAD83-UTM13		Site:SAWDEY GLADYS 1	Rig name no.:BASIC 1524/1524
Event: WELL WORK EXPENSE		Start date: 11/9/2015	End date: Spud date: 6/10/1985
Active datum: RKB @5,010.99usft (above Mean Sea Level)		UWI: 0/2/N/68/W/30/0/SENW/6/0/0/0/0/0/0	
Report no.	Report date	MD (usft)	24 hr summary
1	11/09/2015		SLICKLINE TAG @8034'KB.MIRU BASIC 1524.BLOW WELL DOWN. KILL W/50BBL'S WATER/BIO.ND,NU BOP'S UNLAND TBG@32K. RU EMI TOO H TALLYING W/252 GOOD JNT'S LD 1 BAD 2.375 TBG. TIH RBP SET@4217' W/134JNT'S 2.375 SWI SDFN.
2	11/10/2015		CIRCULATE GAS OUT OF WELL.PSI TEST TO 1000#,GOOD TEST.SPOT 2SX SAND. TOO H 2.375. ND UNLAND 5.5" CSG@105K,MIRU WELDER WELD SLIP COLLAR ONTO 8 5/8, & 5.5' N-80 BELL NIPPLE ON CSG.NU. PU MULE SHOE TIH(ANNULUS)1437' W/44JNT'S.CIRCULATE,PUH TO 1273'. SWI SDFN.
3	11/12/2015		TIH 5JNT'S EOT@1427'. CIRCULATE HOLE.SPOT 20BBL'S 10#. PUH EOT@1210'. MIRU SANJEL PUMP 120SX(29BBL'S) TYPE III CEMENT(FOXHILLS),RDMO. TOO H LD 1.25 TBG. ND RELAND 5.5" CSG@105K. NU, CHANGE OVER EQ. SWI, DRAIN EQ, SDFN.
4	11/13/2015		MIRU FMC WL RIH LOG 4202'-12' W/TOC@530'-BOC@1210', RDMO WL. PSI TEST TO 1000# FOR 15MIN, SWI, SDFN.
5	11/16/2015		TIH TAG SAND ON RBP@4217' W/134JNT'S. CO SAND,RETRIEV/RELEASE RBP. TOO H LD RBP. PU NC,XN NIPPLE,TIH 253JNT'S 2.375 LAND TBG@7979'. BROACH TO ABOVE XN NIPPLE. ND,NU WH. TORQUE PSI TEST WH TO 5000#. SWI. RDMO BASIC 1524.
COMMENTS:			

11/16/15 - WH ALL NEW & FLANGED VALVE TOP. 8" XXH NIPPLES IN CSG.