

On Fri, Sep 18, 2015 at 1:56 PM, Daniel Rabinowitz <drabinow@blm.gov> wrote:
Hi Mark,

I finally finished a review of our files.

We have well files for the following wells:

1. Federal Vance #1-X which also mentions the #1 which was junked. 85 sx. Class B with fly ash bullheaded down casing. Dry hole marker. June 20, 1994
2. Federal Vance #6: Pulled 558', 4.5" casing and cemented with 20 sx. from 630' to 530'. 3 sx. 10' to surface. Dry hole marker. August 11, 1976.
3. Federal #9: Placed 43 sx. across Dakota SS.. Filled hole with 9.5# mud to within 100' of surface, Filled to within 2' of surface with 25 sx. Cut casing to 2' below ground level. No marker erected. Drilled an abandoned. September 5, 1985.
4. Federal Vance #7: Pumped 105 sx of class B with fly ash down the 2-3/8" tubing and up the annulus to the surface. Tubing was not pulled. Marker set. *The production casing in this well was 2-3/8" tubing that was apparently NOT cemented in.* June 20, 1994
5. Federal #10: Pumped (Bullheaded) 70 sx. class B with fly ash down the tubing. Marker set. *The production casing in this well was 2-3/8" tubing that was apparently NOT cemented in.* June 20, 1994
6. Federal #11: Pumped 110 sx. class B with fly ash down the tubing and up the annulus to the surface, laid down 2-3/8" tubing. Finished filling the hole with 3 sx. of ready mix and cemented a proper P&A marker. *The production casing in this well was 2-3/8" tubing that was apparently NOT cemented in.* June 20, 1994.
7. Federal #14: Placed 43 sx. across Dakota SS. – 200'. Filled hole with 9.5# mud to within 100' of surface – Filled hole to within 2' of surface with 25 sx. – cut surface pipe off 2' below surface. No marker erected. Drilled an abandoned. September 9, 1985.

I can give you abandonment dates and location information if that would be helpful. The files are thin! Additionally, I have not heard back from the attorney or Lisa Wright yet. I will follow up next week and see if she wants to talk.

Thanks,

Dan

Dan Rabinowitz
Petroleum Engineer
Bureau of Land Management
Tres Rios Field Office
15 Burnett Court
Durango, CO 81301
drabinow@blm.gov
desk: [970-385-1363](tel:970-385-1363)
fax: [970-375-2338](tel:970-375-2338)