



Re: WPX Energy - CBL Deferment RU 413-5 Request API 05-045-22793

1 message

Jay Krabacher <jay.krabacher@state.co.us>

Fri, Dec 18, 2015 at 2:15 PM

To: "Fechino, Ashlee" <Ashlee.Fechino@wpxenergy.com>

Cc: "david.andrews@state.co.us" <david.andrews@state.co.us>, "Schoeber, Vicki"

<Vicki.Schoeber@wpxenergy.com>, "Ferradas, Nikki" <Nicolette.Ferradas@wpxenergy.com>

Ashlee:

WPX has COGCC concurrence to defer the CBL on this well.

Regards,

Jay Krabacher

On Fri, Dec 18, 2015 at 2:01 PM, Fechino, Ashlee <Ashlee.Fechino@wpxenergy.com> wrote:

Mr. Andrews and Mr. Krabacher,

WPX Energy Rocky Mountain, LLC is requesting CBL deferment on the Federal RU 413-5 located in Section 8, T7S-R93W.

Attached is a temperature survey that was performed after cementing the 4 1/2" production casing on the subject well.

Information pertaining to the request is as follows:

Well:	Federal RU 413-5
API:	05-045-22793
Location:	Section 8 T 7S-R93W
Surface Csg:	9 5/8" set and cemented at 1263'
Production Csg Cement Date:	4 1/2" @ 10,263' – cemented 12/12/15
Cement:	1010 sks
Cement top from survey:	5074' Estimated
Estimated top of gas:	7227' Estimated
Estimated Top Perf:	6800' Estimated
Temp Survey:	12/12/15 Attached
Volume to fill annular:	17 gallons needed to fill following cementing operations.

Please let me know if you need additional information to approve this deferment. After deferment is received, WPX Energy will continue to monitor bradenhead pressure until the CBL has been performed and notify if pressure exceeds 150 psig.

12/12/2015	19:00	6 HR	0 BBL	0 PSI
12/13/2015	01:00	12 HR	0 BBL	0 PSI
12/13/2015	13:00	24 HR	0 BBL	0 PSI
12/14/2015	13:00	48 HR	0 BBL	0 PSI
12/15/2015	13:00	72 HR	0 BBL	0 PSI

Sincerely,

Ashlee Fechino

Regulatory Team Lead

WPX Energy Rocky Mountain, LLC

1058 CR 215 | Parachute, CO 81635

W: 970.623.8915 | C: 970.404.5031

ashlee.fechino@wpxenergy.com

www.wpxenergy.com



—
Jay Krabacher

N W Area Engineer



COLORADO

**Oil & Gas Conservation
Commission**

Department of Natural Resources

P 970.625.2497 x4

C 970.589.6180

796 Megan Ave., Suite 201, Rifle, CO 81650

jay.krabacher@state.co.us | www.colorado.gov/cogcc