

# Halde Redi-Mix, Inc.

Main Office 46321 Hwy. 24 • Burlington, CO 80807 • 719-346-0352  
14105 CO RD 43.3 • Cheyenne Wells, CO 80810  
21637 Hwy. 40/287 Limon, CO 80828

Kerry Halde 719-340-0329

20439

NAME: Wiephing/Fulbertson DATE: 10/26 20 15  
No. Limon

MAIL ADD: Grad Deal # 13 Converse Canyon

DEL'Y ADD: Surface Casing job in Alaka Field DIO CIRCULAR TIME \_\_\_\_\_

QUAN.	UNIT/REFERENCE	UNIT PRICE	AMOUNT
	YDS 100 → SK.	18	1800 00.
	FIBER		
	AIR ENTRAINMENT		
	WATER REDUCER		
9400 lbs	100 sacks & 600 water		
	10 miles delivery		
	Service Charge 2 yds. or less		

TOTAL MINUTES ALLOWED = @ UNLOADING TIME

## GALLONS OF WATER ADDED =

I acknowledge receipt of the above described material. I assume responsibility for reduced strength where water is added. I also assume responsibility for and waive any claim against the seller for damage occasioned by its delivery to the above address.

X CAUTION: Freshly mixed cement, mortar, concrete or ground may cause skin injury. Avoid contact with skin where possible and wash exposed skin area promptly with water. If any cement mixtures get into eyes, rinse immediately and repeatedly with water and get prompt attention.  
KEEP OUT OF REACH OF CHILDREN

MILEAGE <u>10</u>	DRIVER <u>Ken</u>	TRUCK # <u>247</u>
UNLOADING TIME	START	STOP
		TOTAL

Halde Redi-Mix, Inc.

Phone # 719-346-0352 Fax # 719-346-8945  
E-mail haldesand@centurytel.net

Subtotal	\$1,840.00
Sales Tax (4.9%)	\$88.20

<b>Balance Due</b>	<b>\$1,928.20</b>
--------------------	-------------------

Thank you for your business! -- Please remit by the 10th. VISA and MasterCard welcome.



PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT  
CEMENT**

TICKET NUMBER 49539  
LOCATION Oakley, Ca  
FOREMAN Cory D.

Invoice # 806196

DATE		CUSTOMER #		WELL NAME & NUMBER		SECTION		TOWNSHIP		RANGE		COUNTY	
10/27/15		9160		Good Deal # 13		16		10S		55W		Lincoln	
CUSTOMER						Huge N to Road S 2 miles E into Fallow Marsh path to creek							
MAILING ADDRESS													
CITY						STATE		ZIP CODE		TRUCK #		DRIVER	
										731		Cody R	
										693		Rob S.	
										hdp		Aime D.	

JOB TYPE <u>Surface</u>	HOLE SIZE <u>12.75</u>	HOLE DEPTH <u>306'</u>	CASING SIZE & WEIGHT <u>8 5/8 - 24#</u>
CASING DEPTH <u>300</u>	DRILL PIPE	TUBING	OTHER
SLURRY WEIGHT <u>14.8</u>	SLURRY VOL <u>1.24</u>	WATER gal/sk <u>6.5</u>	CEMENT LEFT in CASING <u>30'</u>
DISPLACEMENT <u>17</u>	DISPLACEMENT PSI	MIX PSI	RATE

DISPLACEMENT 17 DISPLACEMENT 1 PSI MIX PSI DATE

REMARKS: Safety meeting - rig up on rig Hole - circulate with rig pump. Hook up to pump truck mix 175 sls 3% CC 2% gel class A cement wash up pump and lines and displace 17 BBL Water shut in rig down

Cement Did Circulate

$$AP_{rot} \propto P_{rot}$$

Thanks Corl & Crew

[illegible]

**Bayin 3737**

### AUTHORIZTION

**TITLE**

DATE \_\_\_\_\_

AUTHORIZATION [Signature] DATE 11/1/00

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



**CONSOLIDATED**  
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT**  
**CEMENT**

TICKET NUMBER **49614**

LOCATION **Opklay Ks**  
REMAN **Jerry V**  
**Miles 5**

**Invoice #806422**

DATE <b>11-20-15</b>	CUSTOMER # <b>9160</b>	WELL NAME & NUMBER <b>Good Deal 13</b>	SECTION <b>16</b>	TOWNSHIP <b>10S</b>	RANGE <b>55W</b>	COUNTY <b>Lincoln</b>
CUSTOMER <b>Weir King Faller ton</b>			Cements to 26 Sto Sign E+S into			
MAILING ADDRESS			TRUCK # <b>753</b>	DRIVER <b>Rory D</b>	TRUCK # <b>528 T127</b>	DRIVER <b>Reth C</b>
CITY	STATE	ZIP CODE				

JOB TYPE **long string** HOLE SIZE **7 7/8** HOLE DEPTH **80.30** CASING SIZE & WEIGHT **5 1/2 17#**  
CASING DEPTH **79.16'** DRILL PIPE TUBING OTHER **PC @ 4608**  
SLURRY WEIGHT **14.2** SLURRY VOL **1.42** WATER gal/sk CEMENT LEFT in CASING **40.49**  
DISPLACEMENT **184/4** DISPLACEMENT PSI MIX PSI RATE

REMARKS: **Safety meeting & rig up on Martin 2.5 run float separator & tankolizer on 3, 4, 6, 7, 8, 11, 14, 17, 20, 23, 24, 25, 26 centralizers on 2, 81 baskets on bottom of 2 & 79 Port Collar on top of 80 @ 4608, circulate vis @ 100 lpm casing to bottom pump ball thru air vis @ 36 pump @ 66/14, 0 ahead mix mud flush with 5 bbl 1/2 @ spacer mix 418 SKS class H 10% salt 2% gel 5% Kalseal 1/4 @ 300 gal release plug wash pump & lines displace with 18 1/4 bbl fresh water final lift 2000# plug landed @ 2500# released back - float held.**

**10 SKS Rathole 10 SKS mousehole.**

**Thank you**  
**Jerry - Cret**

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0455	1	PUMP CHARGE	4600.00	4600.00
CE0002	100	MILEAGE	7.15	715.00
CE0710	20.59	ten mileage delivery	1.75	360.325
CC5801	438 SKS	class H	2.50	1095.00
CC5326	2375 #	salt	2.5	1781.25
CC6077	2190 #	Kalseal	50	1095.00
CC5965	824 #	gel	30	247.20
CC6075	110 #	fluo seal	2.00	220.00
CC6125	500 gal	Mud flush	65	325.00
CP8485	1	5 1/2 AFU float shoe (w)	585.00	585.00
CP8254	1	5 1/2 latch down assy (w)	400.00	400.00
CP8629	2	5 1/2 baskets (w)	385.00	770.00
CP8576	13	5 1/2 turbolizers (w)	110.00	1430.00
CP8554	2	5 1/2 centralizers (w)	81.00	162.00
CP8776	1	5 1/2 Port Collar (I) # 1501146	2850.00	2850.00
		Subtotal		29733.70
		-35		10406.80
		Subtotal		19326.90
		SALES TAX		1082.40
		ESTIMATED TOTAL		20409.30

Revin 3737

AUTHORIZATION **[Signature]**

TITLE **CO-man**

DATE **11/20/15**

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.





**CONSOLIDATED**  
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

4884  
4792  
**Invoice # 206477**  
**FIELD TICKET & TREATMENT REPORT**  
**CEMENT**

TICKET NUMBER **49615**  
LOCATION **Oakley, KS**  
FOREMAN **Jerry V. Wolf**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
11-24-15	9160	Good Deal 13	16	10S	55W	Lincoln
CUSTOMER Weipke & Fuller			CR26 to 2nd hole 3rd hole 5th hole			
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
			753	Cory D		
			56	Keith C		
			714			
			697			
CITY	STATE	ZIP CODE				

JOB TYPE Port Collar HOLE SIZE \_\_\_\_\_ HOLE DEPTH \_\_\_\_\_ CASING SIZE & WEIGHT 5 1/2  
CASING DEPTH \_\_\_\_\_ DRILL PIPE \_\_\_\_\_ TUBING 2 7/8 OTHER PC 9646  
SLURRY WEIGHT 12.5 SLURRY VOL 1.89 WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING \_\_\_\_\_  
DISPLACEMENT 26661 DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE \_\_\_\_\_

REMARKS: Softly meeting & rig up on Codel test for @ 1500 psi operational to 1000 psi  
rate 4661 Pm @ 1100 psi mix 250 Sk 60/40 8% gel 2% CC 1/4" floccul  
was up & displ with 26661 shut down close top & press to 1500 psi held  
run bits in & reverse clean with 50661 H<sub>2</sub>O

*Thank you  
Jerry Wolf*

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0451	1	PUMP CHARGE	1900.00	1900.00
CE0002	100	MILEAGE	7.15	715.00
CE0710	10.75	ton mileage delivery	125	1881.25
CCS831	250 Sk	1/2" blend TIT	17.50	4375.00
CCS325	430 #	CC	1.00	430.00
CC6075	63 #	floccul	2.00	126.00
CCS326	100 #	salt	NC	NC
			Subtotal	9427.25
			-35%	3299.54
			Subtotal	6127.71
			SALES TAX	256.41
			ESTIMATED TOTAL	6384.12

Revin 3737

AUTHORIZATION \_\_\_\_\_ TITLE \_\_\_\_\_ DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.