

WELLBORE DIAGRAM
NGL Water Solutions DJ LLC
NGL C3B
 NENE Sec 29-T4N-R65W
 Weld County, CO
 API - Unassigned

PLANNED

11/9/2015

NOT TO SCALE

PAG

TOPS

K.B.= 4891
 G.L.= 4875
 16

All listed in MD

Parkman - 3765'

Sussex - 4398'

Shannon - 5070'

Niobrara - 6992'

Ft. Hays - 7180'

Codell - 7212'

Carlile - 7222'

9-5/8", 36# J-55 ST&C CSG Set @ 700' (12-1/4" O.H.)
 Cmt'd w/ 204 sx total

X-Bentonite - 7482'

DV Tool @ 7371'
 Cmt'd w/ 614 sx lead, 150 sx tail - TOTAL 764 sks

J-Sand - 7655'

Skull Creek - 7799'

Dakota - 7873'

Morrison - 7996'

Entrada - 8263'

Lykins - 8346'

Permian - 8597'

Forelle - 8704'

Minnekahta - 8749'

4-1/2" tbg
 EOT & Packer @ 8778'

Blaine - 8873'

PBR & TOL @ 8828'

Lyons - 8928'

7" 26# N-80 LT&C CSG Set @ 8928' (8-3/4" O.H.)
 Cmt'd w/ 138 sx (1st stage)

L. Satanka- 9053'

Wolfcamp- 9297'

Amazon - 9345'

Council Grove - 9404'

Admire - 9601'

Virgil - 9641'

Slotted Liner Liner slotted with 2" by 0.040" slots on 6" centers

Missouri - 9895'

Fountain - 9959'

Des Moines - 10079'

Atoka - 10491'

Morrow - 10661'

TD - 10,673'

4-1/2" 11.6# N-80 LT&C Slotted Liner (TOL @ 8828', EOL @ 10,673')
 (6-1/8" O.H.)

MD = 10,673'