

FORM
5
Rev
09/14

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:
400966601

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type Final completion Preliminary completion

OGCC Operator Number: 96850 Contact Name: Whitney Szabo
 Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC Phone: (970) 263-2730
 Address: PO BOX 370 Fax: _____
 City: PARACHUTE State: CO Zip: 81635

API Number 05-045-22346-00 County: GARFIELD
 Well Name: Youberg Well Number: RU 431-7
 Location: QtrQtr: SENE Section: 7 Township: 7S Range: 93W Meridian: 6
 Footage at surface: Distance: 2452 feet Direction: FNL Distance: 379 feet Direction: FEL
 As Drilled Latitude: 39.459772 As Drilled Longitude: -107.808041

GPS Data:
 Date of Measurement: 08/26/2014 PDOP Reading: 1.9 GPS Instrument Operator's Name: J. Kirkpatrick

** If directional footage at Top of Prod. Zone Dist.: 1068 feet. Direction: FNL Dist.: 1178 feet. Direction: FEL
 Sec: 7 Twp: 7S Rng: 93W
 ** If directional footage at Bottom Hole Dist.: 1068 feet. Direction: FNL Dist.: 1178 feet. Direction: FEL
 Sec: 7 Twp: 7S Rng: 93W

Field Name: RULISON Field Number: 75400
 Federal, Indian or State Lease Number: COC50944

Spud Date: (when the 1st bit hit the dirt) 12/18/2014 Date TD: 12/31/2014 Date Casing Set or D&A: 01/01/2015
 Rig Release Date: 01/01/2015 Per Rule 308A.b.

Well Classification:
 Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

Total Depth MD 10097 TVD** 9937 Plug Back Total Depth MD 10002 TVD** 9842

Elevations GR 7737 KB 7763 **Digital Copies of ALL Logs must be Attached per Rule 308A**

List Electric Logs Run:
 RPM/CBL/MUD; No OH logs ran on this well; OH log ran on RU 332-7 API# 05-045-22345, RU 341-7 API# 05-045-22344 and RU 432-7 API# 05-045-22343.

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	18	47.4	0	42	16	0	42	VISU
SURF	13+1/2	9+5/8	32.3	0	1,178	310	0	1,178	VISU
1ST	8+3/4	4+1/2	11.6	0	10,072	1,070	6,060	10,072	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH G	3,897				
MESAVERDE	6,301				Mesaverde top is the williams fork top. .
WILLIAMS FORK	6,301				Williams fork top is the mesaverde top .
CAMEO	9,088				
ROLLINS	9,893				

Comment:

Please note: The "as-drilled" GPS information provided is actual data of the existing well conductor location prior to the big rig spud date.

Well is waiting on completion. Completion of this well is scheduled mid 2016.

The Top of Production footages are estimates and based on the Bottom Hole Location footages because the well has not been completed.

Logs uploaded: 1/7/2016

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Whitney Szabo

Title: Permit Tech II

Date: _____

Email: whitney.szabo@wpenergy.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
Attachment Checklist			
400966657	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400966659	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400966686	Other	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
Other Attachments			
400966644	PDF-CBL 1ST RUN	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400966650	LAS-PULSED NEUTRON	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400966652	PDF-PULSED NEUTRON	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400966655	PDF-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400966669	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)