

EnCana Oil & Gas (USA) Inc.

Well : Grenemeyer Wagner 21-34
Field : Wattenberg
County : Weld County **State** : Colorado
Surface : Lat: 40.0132370 Long: -104.8784710
: 595 FNL, 1948 FWL NWNENW Sec 34 T1N R67W
API # : 05-123-21022
Grd Elev : 5047' GR **KB Elevation**: 5063' KB

Log Tops:

Fox Hills Base 980'
 Sussex 4726'
 Niobrara 7360'
 Codell 7783'
 J Sand 8218'

Well History:

Spud 07/31/02
 TD 08/05/02

Surface Casing

8-5/8" 24# IPSCO J-55
 Surface Casing set @ 1079',
 cmt'd w/ 385 sx. 24 jts.

Workover History:

Original Completion August 2002
 Tubing Repair/Cleanout April 2011
 Upgrade Wellhead February 2014

Stage Cmt 3850'-5706'
 w/ 445 sx
 CBL dated 08/27/02

DV Tool set @ 5706'

TOC @ 6716'
 CBL 08/27/02

Production Casing

4-1/2" 11.6# IPSCO I-80 production
 casing set @ 8377', cmt'd w/ 310 sx.
 199 jts.

Production Tubing

2-3/8" 4.7# J-55 Tubing set
 @ 8207'. 249 jts.

J Sand Perfs

8228'-8234', 8241'-8250', 8258'-8262' w/ 3 SPF
 Frac'd w/ 180,390 gal fluid and 551,280# 20/40
 sand (08/28/02)

PBTD 8340'

TD 8385'

Drawn by:

Tyler Barela

Date:

12/21/2015