

EnCana Oil & Gas (USA) Inc.

Well : Grenemeyer Wagner 22-34
Field : Wattenberg
County : Weld County **State** : Colorado
Surface : Lat: 40.0091400 Long: -104.8786240
: 2034 FNL, 1958 FWL SWSENW Sec 34 T1N R67W
API # : 05-123-20362
Grd Elev : 5073' GR **KB Elevation**: 5083' KB

Log Tops:

Fox Hills Base 980'
 Sussex 4761'
 Niobrara 7379'
 Codell 7806'
 J Sand 8241'

Well History:

Spud 05/16/01
 TD 05/22/01

Surface Casing

8-5/8" 24# J-55 Surface
 Casing set @ 1118', cmt'd
 w/ 785 sx. 25 jts

Workover History:

Original Completion June 2001
 Resin Frac/Cleanout September 2003
 Tubing Repair September 2012
 Upgrade Wellhead March 2014

Stage Cmt 4440'-5364'
 w/ 260 sx
 CBL 06/04/01

DV Tool set @ 5364'

TOC @ 6810'
 CBL 06/04/01

Production Casing

4-1/2" 11.6# I-80 production casing
 set @ 8367', cmt'd w/ 250 sx. 200
 jts.

Production Tubing

2-3/8" J-55 4.7# Tubing set
 @ 8234'. 264 jts.

J Sand Perfs

8252'-8260', 8265'-8292' w/ 2 SPF
 Frac'd w/ 216,097 gal fluid and 527,080# 20/
 40 sand (06/06/01)
 Re-frac'd w/ 13,764 gal fluid and 4,000# 12/
 20 Ac Frac resin coated sand (09/11/03)

PBTD 8306'

TD 8370'

Drawn by:

Tyler Barela

Date:

12/21/2015