



Mr. Scot Donato
Great Western Operating Company LLC
1801 Broadway, Suite 500
Denver, Co. 80202

July 31, 2015

Facility ID: 444442

RE: SAR Followup Sampling, July 2015, Weld County Airport - Drilling Mud Beneficial Re-Use Application Site (portion of E1/2 Section 35, T6N, R65W), MEC # 2015.125b

Attached please find the results of the July 2015 SAR analysis sampling at the Great Western, Drilling Mud Beneficial Re-Use Airport site, Weld County, Co. The SAR sampling focused on the areas that had elevated SAR levels in the April 2015 site sampling.

Specifically, the April 2015 samples with elevated SAR results above the regulatory guideline levels of 12.0 were: POD-C-North (SAR 17.4); POD-C-South (SAR 16.2), and POD-D- North (SAR 12.9). These results were documented in the May 2015 memo.

These POD areas were re-sampled on July 19, 2015. It was anticipated that the above normal rainfall precipitation in April and May may have been assisted in decreasing the SAR ratios.

The July 2015 sampling included the collection of a composite soil sample from the three areas with elevated SAR results in the April 2015 sampling. The composite samples included the collection of 6 aliquot samples from the respective sampling areas. These aliquot portions were mixed together for a representative composite samples. The composite samples were mixed in a pre-cleaned stainless steel bowl and a lab sample was collected in pre-cleaned sampling jar provided by the laboratory.

The site soils were moist and soft. In comparison the site soils at the time of the prior April 2015 were hard and dry.

Sampling Results

The SAR results were below the regulatory guideline levels. Specifically, the SAR results are: POD-C-North (SAR 1.8); POD-C-South (SAR 3.8), and POD-D- North (SAR 4.4).

The results of the sampling are included in the summary tables for the respective sampling Pods.

FINDINGS & RECOMMENDATIONS

The July 2015 SAR sampling results are below the regulatory guideline level of 12.0.

Based on these current results and the prior soil screening sample results, the site soil conditions are in compliance with the COGCC Table 910-1 parameters.

Therefore, since there have been no recent drilling mud application at the site, it is recommended the site closure process continue in accordance with the COGCC regulations. At a minimum, the subsequent closure activities may include regrading and seeding with native grasses. It is suggested that the reseeding include winter grasses or wheat that may be established with limited precipitation.

MEC Inc. appreciates the opportunity to provide you with these environmental consulting services. If you have any further questions, please contact me, 970-381-5951.

Thank you

John Mahoney

John Mahoney
Professional Geologist

WELD LABORATORIES, INC.

1527 First Avenue • Greeley, Colorado 80631
Phone: (970) 353-8118 • Fax: (970) 353-1671
www.weldlabs.com

July 27, 2015

Mahoney Environmental Consulting, Inc.
1601 10th Ave.
Greeley, CO 80631


Laboratory No. E15202-2A
Sample ID: C-South

Results

Calcium (ppm)	110
Magnesium (ppm)	23.1
Sodium (ppm)	168.5
Sodium Adsorption Ratio	3.8
Saturated Pasted Saturation (%)	32.3



Project Manager



Date

WELD LABORATORIES, INC.


1527 First Avenue • Greeley, Colorado 80631
Phone: (970) 353-8118 • Fax: (970) 353-1671
www.weldlabs.com

July 27, 2015


Mahoney Environmental Consulting, Inc.
1601 10th Ave.
Greeley, CO 80631

Laboratory No. E15202-2B
Sample ID: D-North

	Results
Calcium (ppm)	168
Magnesium (ppm)	41.4
Sodium (ppm)	247.5
Sodium Adsorption Ratio	4.4
Saturated Pasted Saturation (%)	37.4



Project Manager



Date

WELD LABORATORIES, INC.

1527 First Avenue • Greeley, Colorado 80631

Phone: (970) 353-8118 • Fax: (970) 353-1671

www.weldlabs.com

July 27, 2015

Mahoney Environmental Consulting, Inc.

1601 10th Ave.

Greeley, CO 80631

Laboratory No. E15202-2C


Sample ID: C-North

Results

Calcium (ppm)	120.5
Magnesium (ppm)	26.9
Sodium (ppm)	84.5
Sodium Adsorption Ratio	1.8
Saturated Pasted Saturation (%)	30.1



Project Manager



Date

Chain of Custody Record

Weld Laboratories, Inc.

1527 1st Avenue Established 1978

Greeley, CO 80631-5936

Phone: (970)353-8118 Fax: (970) 353-1671

J. MATHONEY 2644 2nd CO. MCAS T. NE

TELEPHONE NO. 970-381-5751

COMPANY NAME

MATHEW Environmental

CONTACT NAME

John Mathew

Samplers: Print Name

John Mathew

Signature

[Signature]

ANALYSIS

Project No:

SAMPLE ID	SAMPLE LOCATION	Composite	Grab	Date	Time	Sample Type				No. of Containers and Type	REMARKS									
						Water	Liquid	Oil	Solid											
C-South				7/19/15						1	SAR									
D-North				7/19/15						1										
C-North				7/19/15						1										

COMMENTS:

Relinquished by: (Signature)	Received by: (Signature)	Date	Time
Relinquished by: (Signature)	Received by: (Signature)	Date	Time
Dispatched by: (Signature)	Received for Laboratory by:	Date	Time
Method of Shipment:			

7/21/15 5:07pm 7-21-15 5:10pm

Relinquished by MEC FRC