

**FORM
INSP**Rev
05/11**State of Colorado
Oil and Gas Conservation Commission**1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Inspection Date:

01/25/2016

Document Number:

682400294

Overall Inspection:

SATISFACTORY**FIELD INSPECTION FORM**

Location Identifier	Facility ID	Loc ID	Inspector Name:	On-Site Inspection	2A Doc Num:
	439328	439328	Binschus, Chris	<input type="checkbox"/>	

Operator Information:OGCC Operator Number: 69175Name of Operator: PDC ENERGY INCAddress: 1775 SHERMAN STREET - STE 3000City: DENVER State: CO Zip: 80203

- ☐ THIS IS A FOLLOW UP INSPECTION
- ☐ FOLLOW UP INSPECTION REQUIRED
- ☒ NO FOLLOW UP INSPECTION REQUIRED
- ☐ INSPECTOR REQUESTS FORM 42 WHEN CORRECTIVE ACTIONS ARE COMPLETED

Contact Information:

Contact Name	Phone	Email	Comment
		cogccinspection@pdce.com	ALL INSPECTIONS

Compliance Summary:QtrQtr: NWSW Sec: 26 Twp: 5N Range: 64W**Inspector Comment:**This is a construction inspection. See COGCC comments.**Related Facilities:**

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status	
439320	WELL	XX	10/16/2014	LO	123-40376	Loloff Farms 26H-312	CI	<input checked="" type="checkbox"/>
439326	WELL	XX	10/16/2014	LO	123-40379	Loloff Farms 26H-202	CI	<input checked="" type="checkbox"/>
439330	WELL	XX	10/16/2014	LO	123-40382	Loloff Farms 26G-232	CI	<input checked="" type="checkbox"/>
439331	WELL	DG	04/23/2015	LO	123-40383	Loloff Farms 26G-432	CI	<input checked="" type="checkbox"/>

Equipment:Location Inventory

Special Purpose Pits: _____	Drilling Pits: _____	Wells: <u>4</u>	Production Pits: _____
Condensate Tanks: _____	Water Tanks: <u>4</u>	Separators: <u>4</u>	Electric Motors: _____
Gas or Diesel Motors: _____	Cavity Pumps: _____	LACT Unit: _____	Pump Jacks: _____
Electric Generators: _____	Gas Pipeline: _____	Oil Pipeline: _____	Water Pipeline: _____
Gas Compressors: _____	VOC Combustor: <u>3</u>	Oil Tanks: <u>12</u>	Dehydrator Units: _____
Multi-Well Pits: _____	Pigging Station: _____	Flare: _____	Fuel Tanks: _____

Location

Lease Road:				
Type	Satisfactory/Action Required	comment	Corrective Action	Date

Inspector Name: Binschus, Chris

Signs/Marker:				
Type	Satisfactory/Action Required	Comment	Corrective Action	CA Date

Emergency Contact Number (S/AR): _____ Corrective Date: _____

Comment: _____

Corrective Action: _____

Good Housekeeping:				
Type	Satisfactory/Action Required	Comment	Corrective Action	CA Date

Spills:				
Type	Area	Volume	Corrective action	CA Date
<input type="checkbox"/> Multiple Spills and Releases?				

Fencing:				
Type	Satisfactory/Action Required	Comment	Corrective Action	CA Date

Equipment:				
Type:	#	Satisfactory/Action Required:		
Comment				
Corrective Action				Date:

Venting:	
Yes/No	
Comment	

Flaring:			
Type		Satisfactory/Action Required	
Comment:			
Corrective Action:		Correct Action	Date:

<u>Predrill</u>			
Location ID: 439328			
Site Preparation:			
Lease Road Adeq.:	Pads: SATISFACTORY	Soil Stockpile:	
S/AR: _____			
Corrective Action:		Date:	CDP Num.: _____
Form 2A COAs:			
S/AR: _____	Comment:		
CA: _____	Date: _____		
Wildlife BMPs:			

BMP Type	Comment
Planning	604c.(2).E. Multiwell Pads: This 2A application is for a 4-well pad. No suitable existing locations are in the area. PDC has worked with the landowners to select the proposed site. Location was chosen based on surface owner preference.
Construction	"604c.(2).S. Access Roads: PDC will utilize the lease access road off of CR 52.5 (gravel) for drilling operations and maintenance equipment. The lease access road will be properly constructed and maintained to accommodate for local emergency vehicle access. Dust will be mitigated as necessary on lease access road and CR 52.5. "
Construction	604c.(2).R. Tank Specifications: Condensate storage tanks will be designed, constructed and maintained in accordance with National Fire Protection Association (NFPA) Code 30 (2008 version). PDC will maintain written records to verify proper design, construction and maintenance. All records will be available for inspection by the Director.
Material Handling and Spill Prevention	604c.(2).K. Pit Level Indicators: PDC uses an Electronic Drilling Recorder (EDR) with pit level monitor(s) and alarm(s) for production rigs. Basic level gages are used on steel pits utilized for the surface rig.
Planning	604c.(2).J. BOPE for Well Servicing Operations: All valves will also be tested to maximum rating by a third party prior to being delivered to location. Whenever snubbing operations are being used the snubbing stack will be pressure tested at the same time the BOPE is being tested which consist of a single pipe ram and a annular bag.
Construction	604c.(2).M. Fencing Requirements: The completed wellsites will be surrounded with a fence and gate. PDC personnel will monitor the wellsites regularly upon completion of the wells. Authorized representatives and/or PDC personnel shall be on-site during drilling and completion operations.
Emissions mitigation	604c.(2).C. Green Completions: Flowlines, 48" HLPs, sand traps all capable of supporting green completions as described in rule 805 shall be installed at any Oil and Gas location at which commercial quantities of gas and or oil are reasonable expected to be produced based on existing wells. All green flow back equipment will be able to handle more than 1.5 times the amount of any know volumes in the surrounding field. First sign of salable gas will be put into production equipment and turned down line.
Construction	604c.(2).Q. Guy Line Anchors: Rig guy wires are anchored to the rig's base beam that the rig stands on, temporary and permanent anchors will not be set on this location.
Planning	804. Visual Impact: Production facilities, regardless of construction date, which are observable from any public highway will be painted with uniform, non-contrasting, non-reflective color tones (similar to the Munsell Soil Color Coding System), and with colors matched to but slightly darker than the surrounding landscape.
General Housekeeping	604c.(2).N. Control of Fire Hazards: PDC will ensure that any material that might be deemed a fire hazard will be will remain no less than twenty-five (25) feet from the wellhead(s), tanks and separator(s). PDC installs automation equipment for tank level and pressure monitoring inside the bermed area that complies with API RP 500 classifications and with the current national electrical code as adopted by the State of Colorado.
Drilling/Completion Operations	604c.(2).O. Loadlines: All loadlines shall be bullplugged or capped.

Noise mitigation	604c.(2).A. Noise: WELL PAD: PDC has conducted baseline noise surveys for all drilling rigs that are being contracted and has also conducted a baseline noise survey for hydraulic fracture stimulation operations on a representative horizontal well. These baseline surveys are utilized for site specific noise modeling to determine if any mitigation measures are warranted. A review was conducted to identify potential receptors within 1000 feet of the proposed pad site. There are 4 building units of concern located north 249 feet south-west , 568 feet south-west, 641 feet south-west and 726 feet south-west of the proposed pad. Based on the results and terrain, projected noise levels are anticipated to exceed the Light Industrial Zone standard of 65 decibels (db) at the receptors location. Therefore, noise mitigation will be necessary and will be installed south of the proposed pad to prior to drilling and completion operations. Methods of noise mitigation shall include but not be limited to hay bales, noise walls, or customized semi-trailers. PRODUCTION FACILITIES: It is not anticipated that noise mitigation will be necessary at the proposed tank battery location. After construction is completed, equipment installed and production begins, noise levels will be assessed to determine if mitigation measures will be required to be compliant with Rule 802.
Storm Water/Erosion Control	This Stormwater Management Plan contains required elements associated with PDC's construction activities, as defined in the CDPS General Permit for Stormwater Discharges Associated with Construction Activity, Authorization to Discharge Under the Colorado Discharge Permit System (Permit No. COR-030000, re-issued and effective July 1, 2007).BMPs for sediment and erosion control will be accomplished through a combination of construction techniques, vegetation and re-vegetation, administrative controls, and structural features.
Planning	604c.(2).L. Drill Stem Tests: PDC does not conduct drill stem tests, but will seek prior approval from the director if a drill stem test will be preformed.
Construction	604c.(2).G. Berm Construction: Containment berms will be constructed using steel rings, designed and installed to prevent leakage and resist degradation from erosion or routine operation. Secondary containment will be constructed with a geosynthetic liner that contains all tanks and flowlines at this location and will be mechanically connected to the steel ring to prevent leakage. Operator will implement site-specific best management practices in accordance with good engineering practices, including, but not limited to, construction of a berm or diversion dike, site grading, or other comparable measures, sufficient to protect the down gradient water sources - ditch located 300 feet west from the nearest well head.
Material Handling and Spill Prevention	604c.(2).F. Leak Detection Plan: See attached.
Odor mitigation	805.b(1)-(c) Odors and Dust: Oil and gas facilities and equipment will operate in a manner that odors and dust do not constitute a nuisance or hazard to public welfare. Odors: Oil and gas operations will be in compliance with the Department of Public Health and Environment, Air Quality Control Commission, Regulation No. 2 Odor Emission, 5 C.C.R. 1001-4, Regulation No. 3 (5 C.C.R. 1001-5), and Regulation No. 7 Section XVII.B.1 (a-c) and Section XII. Dust; PDC will employ practices for control of fugitive dust caused by operations include but not limited to the use of speed restrictions, regular road maintenance, restriction of construction activity during high-wind days, and silica dust controls when handling sand used in hydraulic fracturing operations. When necessary, PDC coordinates dust mitigation with the county on gravel roads, places road base where allowed by surface owner around tanks and wellheads to minimize dust, and will water the roads and locations when dry. In addition, automation is used on all new wells to minimize truck traffic.
General Housekeeping	604c.(2).T. Well Site Cleared: The wellsite will be cleared of all non-essential equipment within ninety (90) days after all wells associated with the pad have been plugged and abandoned.
Traffic control	604c.(2).D. Traffic Plan: If required by the local government, a traffic plan will be coordinated with the local jurisdiction prior to commencement of operations.
Planning	604.c.(2).W. Site Specific Measures: Lights should be turned downward and away from building units within the 1,000 foot buffer area. Dust mitigation will be provided as necessary on lease access roads.

Inspector Name: Binschus, Chris

General Housekeeping	604c.(2).P. Removal of Surface Trash: A commercial size trash bin for removing debris will be located on site. This bin will be for use by all parties affiliated with the operation.
Planning	604c.(2).V. Development From Existing Well Pads: An existing pad was not available to utilize to develop these wells.
Planning	604c.(2).I. BOPE Testing for Drilling Operations: PDC's contractors will supply a double ram BOPE (Blinds and pipes). BOPE is always function tested and all seals and ram block rubbers are inspected. After installation of the BOPE, PDCE conducts a pressure test on the BOPE at a low pressure of (200-400 psi) and a high pressure test with a third party tester, all tests are digitally recorded and any failed equipment or seals are replaced and re-tested.
Planning	604c.(2).U. Identification of Plugged and Abandoned Wells: Pursuant to rule 319.a.(5)., once the well has been plugged and abandoned, PDC will identify the location of the wellbore with a permanent monument that will detail the well name and date of plugging.

S/AR: _____ Comment: _____

CA: _____ Date: _____

Stormwater:

Erosion BMPs	Present	Other BMPs	Present
DITCHES	Yes		

S/AR: SATISFACTORY

Corrective Action: _____ Date: _____

Comments: Erosion BMPs: Topsoil salvage in process. Need to stabilize topsoil stockpile upon completion of topsoil separation.

Other BMPs: _____

Comment: _____

Staking:

On Site Inspection (305):

Surface Owner Contact Information:

Name: _____ Address: _____
Phone Number: _____ Cell Phone: _____

Operator Rep. Contact Information:

Landman Name: _____ Phone Number: _____
Date Onsite Request Received: _____ Date of Rule 306 Consultation: _____
Request LGD Attendance: _____

LGD Contact Information:

Name: _____ Phone Number: _____ Agreed to Attend: _____

Summary of Landowner Issues:

Summary of Operator Response to Landowner Issues:

Onsite Inspection Memorandum Summarizing Discussions at Inspection as Attachment:

Facility

Facility ID: 439320 Type: WELL API Number: 123-40376 Status: XX Insp. Status: CI

Inspector Name: Binschus, Chris

Facility ID: 439326 Type: WELL API Number: 123-40379 Status: XX Insp. Status: CI

Facility ID: 439330 Type: WELL API Number: 123-40382 Status: XX Insp. Status: CI

Facility ID: 439331 Type: WELL API Number: 123-40383 Status: DG Insp. Status: CI

Environmental

Spills/Releases:

Type of Spill: Description: Estimated Spill Volume:
Comment:
Corrective Action: Date:
Reportable: GPS: Lat Long
Proximity to Surface Water: Depth to Ground Water:

Water Well:

Lat Long
DWR Receipt Num: Owner Name: GPS :

Field Parameters:

Sample Location:

Emission Control Burner (ECB):

Comment:

Pilot: Wildlife Protection Devices (fired vessels):

Reclamation - Storm Water - Pit

Interim Reclamation:

Date Interim Reclamation Started: Date Interim Reclamation Completed:

Land Use: IRRIGATED

Comment:

1003a. Waste and Debris removed?

CM
CA CA Date

Unused or unneeded equipment onsite?

CM
CA CA Date

Pit, cellars, rat holes and other bores closed?

CM
CA CA Date

Guy line anchors marked?

CM
CA CA Date

Inspector Name: Binschus, Chris

- 1003b. Area no longer in use? _____ Production areas stabilized ? _____
- 1003c. Compacted areas have been cross ripped? _____
- 1003d. Drilling pit closed? _____ Subsidence over on drill pit? _____
- Cuttings management: _____
- 1003e. Areas no longer needed for drilling or subsequent operations for have been re-vegetated to 80% of pre-existing? _____
- Production areas have been stabilized? _____ Segregated soils have been replaced? _____

RESTORATION AND REVEGETATION

Cropland

Top soil replaced _____ Recontoured _____ Perennial forage re-established _____

Non-Cropland

Top soil replaced _____ Recontoured _____ 80% Revegetation _____

1003 f. Weeds Noxious weeds? _____

Comment: _____

Overall Interim Reclamation _____

Final Reclamation/ Abandoned Location:

Date Final Reclamation Started: _____ Date Final Reclamation Completed: _____

Final Land Use: IRRIGATED

Reminder: _____

Comment: _____

Well plugged _____ Pit mouse/rat holes, cellars backfilled _____

Debris removed _____ No disturbance /Location never built _____

Access Roads Regraded _____ Contoured _____ Culverts removed _____

Gravel removed _____

Location and associated production facilities reclaimed _____ Locations, facilities, roads, recontoured _____

Compaction alleviation _____ Dust and erosion control _____

Non cropland: Revegetated 80% _____ Cropland: perennial forage _____

Weeds present _____ Subsidence _____

Comment: _____

Corrective Action: _____ Date _____

Overall Final Reclamation _____ Well Release on Active Location ☐ Multi-Well Location ☐

Storm Water:

Loc Erosion BMPs	BMP Maintenance	Lease Road Erosion BMPs	Lease BMP Maintenance	Chemical BMPs	Chemical BMP Maintenance	Comment

S/A/V: _____ Corrective Date: _____

Comment: _____

CA: _____

Pits: ☐ NO SURFACE INDICATION OF PIT

COGCC Comments

Comment	User	Date
Stormwater and sediment control BMPs installed before construction.	binschusc	01/28/2016
Topsoil salvage in process. Need to stabilize topsoil stockpile upon completion of topsoil separation.		
Refer to attached photos in Doc.#682400295.		

Attached Documents

You can go to COGCC Images (<https://cogcc.state.co.us/weblink/>) and search by document number:

Document Num	Description	URL
682400294	INSPECTION APPROVED	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=3771654
682400295	Location Photos	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=3771653