

**FORM**  
**5**  
Rev  
09/14

**State of Colorado**  
**Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:  
400973425

Date Received:

**DRILLING COMPLETION REPORT**

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type  Final completion  Preliminary completion

OGCC Operator Number: 47120 Contact Name: Jennifer Thomas  
 Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6808  
 Address: P O BOX 173779 Fax: \_\_\_\_\_  
 City: DENVER State: CO Zip: 80217-

API Number 05-123-41052-00 County: WELD  
 Well Name: WILSON RANCH Well Number: 33C-27HZ  
 Location: QtrQtr: SESE Section: 26 Township: 4N Range: 68W Meridian: 6  
 Footage at surface: Distance: 608 feet Direction: FSL Distance: 349 feet Direction: FEL  
 As Drilled Latitude: 40.279049 As Drilled Longitude: -104.961975

GPS Data:  
 Date of Measurement: 10/19/2015 PDOP Reading: 2.0 GPS Instrument Operator's Name: Sergio Del Carmen

\*\* If directional footage at Top of Prod. Zone Dist.: 1050 feet. Direction: FSL Dist.: 1008 feet. Direction: FEL  
 Sec: 26 Twp: 4N Rng: 68W  
 \*\* If directional footage at Bottom Hole Dist.: 1151 feet. Direction: FSL Dist.: 486 feet. Direction: FWL  
 Sec: 27 Twp: 4N Rng: 68W

Field Name: WATTENBERG Field Number: 90750  
 Federal, Indian or State Lease Number: \_\_\_\_\_

Spud Date: (when the 1st bit hit the dirt) 10/13/2015 Date TD: 11/01/2015 Date Casing Set or D&A: 11/03/2015  
 Rig Release Date: 12/10/2015 Per Rule 308A.b.

Well Classification:  
 Dry  Oil  Gas/Coalbed  Disposal  Stratigraphic  Enhanced Recovery  Storage  Observation

Total Depth MD 17004 TVD\*\* 7416 Plug Back Total Depth MD 16900 TVD\*\* 7418

Elevations GR 5072 KB 5092 **Digital Copies of ALL Logs must be Attached per Rule 308A**

List Electric Logs Run:  
CBL, GR

**CASING, LINER AND CEMENT**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42.1	0	60	28	0	60	VISU
SURF	13+1/2	9+5/8	36	0	1,857	741	0	1,857	VISU
1ST	8+1/2	5+1/2	17	0	16,989	2,410	26	16,989	CBL

### STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

### FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	4,301				
SHARON SPRINGS	7,094				
NIOBRARA	7,141				
FORT HAYS	7,570				
CODELL	7,639				
CARLILE	7,793				

Comment:

Due to anti-collision needs and the variability of directional drilling, our as-drilled BHL could be different than the permitted. Per rule 317.p Exception, no open hole logs were run on this pad. Cased hole compensated neutron logs were run as an alternate log on the Whisper Rock 4C-25HZ API# 12341069.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Jennifer Thomas

Title: Regulatory Specialist Date: \_\_\_\_\_ Email: rscdjpostdrill@anadarko.com

### Attachment Check List

Att Doc Num	Document Name	attached ?	
<b>Attachment Checklist</b>			
400973487	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400973488	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<b>Other Attachments</b>			
400976229	LAS-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400976230	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400979722	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400981202	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400981203	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)