

FORM
5Rev
09/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400983724

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 8960

Contact Name: Jessica Azzolina

Name of Operator: BONANZA CREEK ENERGY OPERATING COMPANY

Phone: (720) 440-6100

Address: 410 17TH STREET SUITE #1400

Fax: (720) 279-2331

City: DENVER State: CO Zip: 80202

API Number 05-123-42350-00

County: WELD

Well Name: State Pronghorn

Well Number: 42-32-31MRLNB

Location: QtrQtr: NENE Section: 32 Township: 5N Range: 61W Meridian: 6

Footage at surface: Distance: 1290 feet Direction: FNL Distance: 711 feet Direction: FEL

As Drilled Latitude: 40.361020 As Drilled Longitude: -104.226070

GPS Data:

Date of Measurement: 01/13/2016 PDOP Reading: 1.8 GPS Instrument Operator's Name: Marc Mayer

** If directional footage at Top of Prod. Zone Dist.: 2022 feet. Direction: FNL Dist.: 682 feet. Direction: FEL

Sec: 32 Twp: 5N Rng: 61W

** If directional footage at Bottom Hole Dist.: 2004 feet. Direction: FNL Dist.: 2220 feet. Direction: FEL

Sec: 31 Twp: 5N Rng: 61W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number: 1178.10

Spud Date: (when the 1st bit hit the dirt) 11/07/2016 Date TD: 11/28/2015 Date Casing Set or D&A: 11/29/2015

Rig Release Date: 12/03/2015 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 13343 TVD** 6033 Plug Back Total Depth MD 13343 TVD** 6033

Elevations GR 4565 KB 4582 Digital Copies of ALL Logs must be Attached per Rule 308A ☒

List Electric Logs Run:

Mud, CBL, Gamma, (OH log ran on the State Pronghorn V-32-31MRLNB, API # 05-123-42353)

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	13+1/2	9+5/8	36	0	1,416	630	0	1,416	CALC
1ST	8+3/4	7	26	0	6,539	790	0	6,539	CBL
1ST LINER	6+1/8	4+1/2	11.6	5622	13,336				VISU

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	3,209		NO	NO	
SHARON SPRINGS	6,017		NO	NO	
NIOBRARA	6,221		NO	NO	No Shannon or Sussex present

Comment:

OH log ran on the State Pronghorn V-32-31MRLNB, API # 05-123-42353

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Jessica Azzolina

Title: Drilling Technician

Date: _____

Email: jazzolina@bonanzacrk.com

Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
400983760	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
400983765	Directional Survey **	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
400983738	PDF-MUD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
400983740	LAS-MUD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
400983750	PDF-GAMMA RAY	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
400983752	LAS-GAMMA RAY	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
400983755	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
400983759	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
400983766	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)