

Light, Cheryl

From: Schlagenhauf - DNR, Mark <mark.schlagenhauf@state.co.us>
Sent: Monday, January 11, 2016 1:40 PM
To: Moreland, Jane Ann
Cc: Light, Cheryl; Morales, Luis [Naill Services Inc.]; Green, Doreen
Subject: Re: DONALD VYNCKIER GAS UNIT #B #2

Jane Ann,

No objection subject to the following COA:

The additional cement referenced shall be placed as indicated and comply with Rule 317.j. The placed cement shall be verified with a CBL and documented with a Form 5 Drilling Completion Report.

Mark Schlagenhauf P.E.
Engineering Integrity Supervisor

On Mon, Jan 11, 2016 at 12:05 PM, Moreland, Jane Ann <JaneAnn.Moreland@anadarko.com> wrote:

Mark,

Thank you for time today – here is the follow up to confirm the remedial work on Donald Vynckier Unit #B #2 (API# 05-123-19175)

We are experiencing Bradenhead issues on this well up to 40 psi and producing liquids. We plan on cementing from 1473' to 740' (200' below the FHM @ 1273' and 100' above the casing shoe @ 840') - cement behind pipe. We received your verbal confirmation to proceed, please confirm.

Please let us know if you need anything else.

Thanks,

Jane Ann Moreland

Jane Ann Moreland

Production Engineer | Wattenberg

Anadarko Petroleum Corporation

501 North Division Blvd. | Platteville, Colorado 80651

Office 1057 | [\(970\) 515-1135](tel:(970)515-1135)

[Click here for Anadarko's Electronic Mail Disclaimer](#)