

## WELL COMPLETION REPORT

**OPERATOR:** Antelope Energy Company, LLC  
**WELL NAME:** Nelson Ranches A-#7  
**LOCATION:** NW/4 SE/4 (2280' fsl, 2280' fel  
Section 20-T10N-R58W  
Weld County, Colorado  
**CONTRACTOR:** Evertson Well Service  
**ELEVATIONS:** 4807' GL, 4818' KB  
**T.D.** 6656'  
**P.B.T.D.** 6639'  
**CASING DETAIL:** 8 5/8", 24# - set @ 304'  
4 1/2", 11.6# M-75 - set @ 6656' w/ 150 sks  
**PERFS:** D Sand 6553 - 6558' - 4 SPF (20 holes)

### CONFIDENTIAL

#### REPORT

##### DATE

##### DETAIL

08-11-98 MI Evertson Well Service. Had trouble spotting in because of mud. RU. Unload 2 3/8" tbg from Curley's onto sills. RU to PU tbg. PU and tallied 2 3/8" tbg w/ bit and scraper. Tagged bottom @ 6639' KB. PU 1' off bottom. Landed tbg. RU to tbg swab. Swabbed. IFL @ surface, FFL @ 1600'. SDFN.

08-12-98 Continue to swab well down. Pumped 20.04 bbls lease oil down csg. Finished swabbing well until last run was oil. Pulled tbg. RU Schlumberger to perforate. Perforated well w/ approx. 18 bbls oil in hole @ 6553 - 6558', 4 spf @ 60° phase, 20 holes, 22 gram shots. Ran tbg w/ Model R packer and seating nipple. Set packer @ 6534' KB. Landed tbg and packed off well head. Shut well in. SDFN.

08-13-98 Checked tbg pressure - had slight blow. RU to swab.

Time	Fluid Level	Bbbs/ Hr.	Total Bbbs	% Oil	Bbbs to Recover	Comments
8:00	5000'			100%	6.20	
9:00	Pkr	5.12	5.12	100%	1.08	Good gas after 1 <sup>st</sup> run
10:00	"	0.00	5.12		1.08	No fluid
11:00	"	0.00	5.12		1.08	No fluid entry

Shut well in. SDFN.