

WELLBORE DIAGRAM - CURRENT

Formation Tops:
Wasatch (Surface)

Williams Fork (3508)

Top Gas (4493)

Cameo (5940)

Rollins (6451)

Cozette (6726)

Corcoran (6967)

Watson Ranch B 24AWI-17-07-95

Ursa Operating Company LLC
Piceance Basin
Garfield County, CO
API: 05045-22801-00

Updated: 3-23-16 DPY

Section 17, T7S, R95W

BHL: 1047 FSL, 1978 FWL
SHL: 1047 FSL, 1978 FWL
GL: 5585'
KB: 5602'

Surface Casing: 9-5/8" 36# J-55
Set @ 1741
Cemented to surface

TOC @ 2100 (from CBL)

Injection Tubing: 2-7/8" 6.50# L-80
Set @ 6674 KB
Arrow-Set Packer @ 6665

Stage 02 Perfs: 6734 - 6936
"Cozette"
4 spf, 0.44 EHD, 80 Holes

Stage 01 Perfs: 6983 - 7175
"Corcoran"
4 spf, 0.44 EHD, 80 Holes

PBTD @ 7330

Production Casing: 5-1/2" 17# P-110
Set @ 7373
TOC @ 2100 (from CBL)

