



|                                    |                     |  |   |               |                  |              |
|------------------------------------|---------------------|--|---|---------------|------------------|--------------|
| <b>COMPANY</b>                     |                     |  |   |               | <b>DATE</b>      |              |
| Schneider Energy Services, Inc     |                     |  |   |               | 2/16/16          |              |
| <b>LEASE</b>                       |                     |  |   |               |                  |              |
| Knappe #3                          |                     |  |   |               |                  |              |
| <b>CASING</b>                      | <b>Size</b>         | <b>Weight</b>                            | <b>Grade</b>                                | <b>Thread</b> | <b>Depth</b>     |              |
|                                    | 8-5/8"              | 24                                       | J-55  | LT&C          | 215              |              |
| <b>Casing</b>                      | <b>Size</b>         | <b>Weight</b>                            | <b>Grade</b>                                | <b>Thread</b> | <b>Depth</b>     |              |
|                                    | 4-1/2"              | 10.5                                     | J-55  | LT&C          | 6825             |              |
| <b>Tubing</b>                      | <b>First String</b> | <b>Size</b>                              | <b>Weight</b>                               | <b>Grade</b>  | <b>Thread</b>    | <b>Depth</b> |
|                                    |                     | 2-3/8"                                   | 4.7   | J-55          | 8rd EUE          | 6680         |
| <b>Prepared for: COGCC</b>         |                     |  | <b>Perforations: D-Sand 6689' to 6694'.</b> |               |                  |              |
| <b>CURRENT WBD.</b>                |                     |  |   |               |                  |              |
| <b>ITEM No#</b>                    | <b>Length</b>       | <b>Description</b>                       |   | <b>ID</b>     | <b>OD</b>        | <b>Depth</b> |
| 1                                  | 215.00              | 8-5/8", 24# Surface casing landed @ 215' |   |               |                  | -215.00      |
| 2                                  |                     | Top of cement @ 5100' (Calculated)       |   |               |                  |              |
| 3                                  |                     | 2-3/8" tubing landed @ 6680'             |   |               |                  |              |
| 4                                  |                     | D-Sand Perfs 6689' to 6694'              |   |               |                  |              |
| 5                                  | 6825.00             | 4-1/2", 10.5# casing set @ 6285          |   |               |                  | 6825.00      |
| <b>PREPARED BY: Jeff Schneider</b> |                     |  |   | <b>PHONE:</b> |                  |              |
|                                    |                     |  |   | 970-381-9588  |                  |              |
| <b>OFFICE</b>                      |                     |  | <b>PHONE</b>                                |               | <b>INVOICE #</b> |              |
|                                    |                     |  |   |               |                  |              |