

FORM  
2

Rev  
08/13

## State of Colorado

### Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400956696

#### APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_

Refiling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Date Received:

12/29/2015

Well Name: Hebron

Well Number: 0780 4-7H

Name of Operator: SANDRIDGE EXPLORATION & PRODUCTION LLC

COGCC Operator Number: 10598

Address: 123 ROBERT S KERR AVE

City: OKLAHOMA CITY

State: OK

Zip: 73102

Contact Name: Kimberly Rodell

Phone: (303)942-0506

Fax: ( )

Email: krodell@upstreampm.com

#### RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20150119

#### WELL LOCATION INFORMATION

QtrQtr: NWNW Sec: 17 Twp: 7N Rng: 80W Meridian: 6

Latitude: 40.584658

Longitude: -106.405128

Footage at Surface: 37 feet FNL/FSL FNL 554 feet FEL/FWL FWL

Field Name: NORTH PARK HORIZONTAL  
NIOBRARA

Field Number: 60120

Ground Elevation: 8149

County: JACKSON

GPS Data:

Date of Measurement: 11/19/2015 PDOP Reading: 1.3 Instrument Operator's Name: Chad Meiers

If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FEL/FWL

512 FNL 350 FEL 300 FNL 350 FEL  
Sec: 7 Twp: 7N Rng: 80W Sec: 7 Twp: 7N Rng: 80W

#### LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☐ is the mineral owner beneath the location.  
(check all that apply) ☐ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: Surface Surety ID:

## LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

T7N R80W Sec. 7: SENE, part of SW, SE, and more particularly described by metes and bounds.

Total Acres in Described Lease: 304 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

## CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 2586 Feet  
Building Unit: 2600 Feet  
High Occupancy Building Unit: 5280 Feet  
Designated Outside Activity Area: 5280 Feet  
Public Road: 532 Feet  
Above Ground Utility: 339 Feet  
Railroad: 5280 Feet  
Property Line: 554 Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

## SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 770 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 300 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

## SPACING & FORMATIONS COMMENTS

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	531-18	640	Sec. 7: All

## DRILLING PROGRAM

Proposed Total Measured Depth: 12117 Feet

Distance from proposed wellbore to nearest existing or permitted wellbore belonging to another operator:

770 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	46	0	90	100	90	0
SURF	12+1/4	9+5/8	39	0	2500	576	2500	0
1ST	8+3/4	5+1/2	20	0	12117	2006	12117	2300

☐ Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

## OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments

Top of Production Zone is the Top of Niobrara and not the Landing Point. The distance from the proposed wellbore to the nearest completed portion of offset wellbore permitted or completed in the same formation and the nearest existing or permitted wellbore belonging to another operator were both taken from the Hebron 1-18H, API No. 05-057-06501, currently owned and operated by EE3 LLC. There are multiple leases that cover this location. The horizontal wellbore crosses this lease line and conforms to the Drilling and Spacing Unit and its setbacks. This permit is being submitted with a revised Oil and Gas Location Assessment. SandRidge will be adding additional wells and facilities to this location.

This application is in a Comprehensive Drilling Plan \_\_\_\_\_ No \_\_\_\_\_ CDP #: \_\_\_\_\_

Location ID: 324757

Is this application being submitted with an Oil and Gas Location Assessment application? \_\_\_\_\_ Yes \_\_\_\_\_

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Kimberly Rodell

Title: Permit Agent Date: 12/29/2015 Email: krodell@upstreampm.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 2/17/2016

Expiration Date: 02/16/2018

API NUMBER

05 057 06545 00

## Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### COA Type

### Description

	1) Operator shall comply with the most current revision of the Northwest Notification Policy.
	2) Operator shall provide cement coverage from the production casing shoe (5+1/2" First String) to a minimum of 200' above the surface casing shoe to provide full isolation of the Coalmont Formation. Verify production casing cement coverage with a cement bond log. Changed First String cement top from a null value to 2300' (200' above proposed surface casing shoe depth of 2500').

## Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Drilling/Completion Operations	One of the first wells drilled on the pad will be logged with open-hole Resistivity Log and Gamma Ray Log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "No open-hole logs were run" and shall clearly identify (by API#, well name & number) the well in which open-hole logs were run.

Total: 1 comment(s)

## Applicable Policies and Notices to Operators

Policy
NW Colorado Notification Policy. <a href="http://cogcc.state.co.us/documents/reg/Policies/nw_notification_procedures.pdf">http://cogcc.state.co.us/documents/reg/Policies/nw_notification_procedures.pdf</a>
Notice Concerning Operating Requirements for Wildlife Protection. <a href="http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf">http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf</a>

## Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400956696	APD APPROVED
400959107	DIRECTIONAL DATA
400960939	OffsetWellEvaluations Data
400960940	WELL LOCATION PLAT
400960941	DEVIATED DRILLING PLAN
400960944	OTHER
400960950	SURFACE AGRMT/SURETY
400961652	DRILLING PLAN
400991355	OFFSET WELL EVALUATION
400991361	FORM 2 SUBMITTED

Total Attach: 10 Files

## General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final review complete.	2/17/2016 11:28:40 AM
Engineer	Operator (Spence Laird) requested a change of the surface casing setting depth and cement volume via email on 2/11/2016, as follows:  Please correct the surface casing depth to 2500' Top of cement – surface Estimated volume gauge hole + 50% excess Lead: 376 sx Halliburton SwiftCem @ 2.18 ft³/sk Tail: 200 sx Halliburton SwiftCem @ 1.76 ft³/sk Top Out (if needed): 100 sx @ 1.76 ft³/sk  COGCC Engineering staff changed this form as follows: Surface Casing Setting Depth and Cement Bottom = 2500', and Surface Casing Cement Volume = 576 sacks.	2/16/2016 6:11:25 PM

Permit	<p>With operator approval, revised top of production zone footages to the landing point footages indicated on the well location plats, entered approved spacing order, removed operator comment regarding top of production zone and correct distance to unit boundary to 300' from 5280'.</p> <p>Permit task passed.</p>	2/11/2016 3:35:27 PM
Permit	Waiting on operator to provide a revised distance to unit boundary.	2/4/2016 10:01:45 AM
Engineer	<p>At the time this form was submitted, the operator stated in their comment, "The distance from the proposed wellbore to the nearest...existing or permitted wellbore belonging to another operator [was] taken from the Hebron 1-18H, API No. 05-057-06501, currently owned and operated by EE3 LLC." As of 1/8/2016, SandRidge is the operator of record for Hebron 1-18H. The next closest "Distance from proposed wellbore to nearest existing or permitted wellbore belonging to another operator, including plugged wells" is Trownsell 7-80 #8-1 (057-06440), a dry and abandoned well previously operated by Red Willow Production, LLC, approximately 1160' east of this proposed well.</p>	1/8/2016 12:43:13 PM
Engineer	<p>Offset Well Evaluation: COGCC evaluated a 1,500-foot buffer around the planned wellbore paths of ten proposed wells on this pad. The nine offset wells shown on the operator's offset well evaluation are within the 1,500-foot buffer. Offset mitigation is required for one of the nine wells shown below: Hebron #7-17H (057-06472), which is listed first. The offset mitigation is only required for stimulation of the proposed wells Mutual 0780 2-8H (Form 2 #400958252) and Mutual 0780 3-8H (Form 2 #400958361).</p> <p>Evaluated offset horizontal producing (PR) well Hebron #7-17H (057-06472), TD at 12181' and completed in the Niobrara Formation. First String intermediate casing cement coverage appears to extend above the surface casing shoe (set at 1046'), with adequate isolation of the Niobrara production zone (top perforation at 8062' and First String shoe at 7338'). The First String cement bond log (CBL) for this well was not run across the entire Coalmont Formation, and therefore cement quality and coverage is uncertain in the unlogged interval from 1232' to 4790'. A production liner is cemented across the Niobrara completion and up into the First String. Offset mitigation required because of the uncertain cement coverage in the lower portion of the Coalmont Formation for the Mutual 7-17H well.</p> <p>Evaluated offset dry and abandoned (DA) well Evans 7-80 17-1 (05-057-06439), surface casing set at 313' and cemented to surface, well TD in Pierre Shale at 3886'. Cement plug set in open hole across Pierre Shale top at 3761' (50 sx from 3770' to 3600'). Other open hole plugs set in the Coalmont Formation to isolate coal seams (60 sx from 3550' to 3350', 30 sx from 3250' to 3100', and 120 sx from 2600' to 2275'). A kick-off plug was set for a sidetrack to core and set production casing (80 sx from 2300' to 2130'). The Sidetrack 01 was TD in Pierre Shale at 3860', with production casing set at the same depth and a top of cement at 2500'. Well was completed in the Coalmont Formation, but it did not produce (3540' top perforation). A CIBP was set in casing at 3490' with 2 sx cement on top. Production casing was cut and pulled at 2320'. A cement plug was set across the production casing stub (100 sx from 2420' to 2220'), an open-hole cement plug was set with 100 sx from 1400' to 1215', a cement plug was set across the surface casing shoe (100 sx from 400' to 220'), and 20 sx was set in the casing at surface. Well did not penetrate the Niobrara Formation, and the Coalmont Formation is adequately isolated. No offset mitigation required. This well plots within 150' of the wellbore path for the proposed Castle 0780 2-17H20 well (Form 2 #400959573). Anti-collision is not required because of vertical separation exceeding 150' (this well terminates in a shallower formation).</p> <p>Evaluated offset DA well Trownsell 7-80 8-1 (05-057-06440), surface casing set at 321' and cemented to surface, well TD in Pierre Shale at 4386'. Well was dry and abandoned. Cement plug set in open hole across Pierre Shale top at 4217' (134 sx from 4250' to 3850'). Other open hole plugs set in the Coalmont Formation to isolate coal seams (84 sx from 3650' to 3400', 84 sx from 2550' to 2300', 168 sx from 1850' to 1350', and 110 sx from 1200' to 950'). A kick-off plug was set for a sidetrack to core and set production casing (130 sx from 800' to 450'). Production casing was</p>	1/8/2016 10:26:43 AM

	<p>set at 2485' and cemented to surface in the Sidetrack 01 wellbore. The well was not completed. Cement plugs were set in the production casing (20 sx from 2440' to 2260', 15 sx from 1525' to 1395', 25 sx from 430' to 210' across surface casing shoe, and 10 sx at surface). Well did not penetrate the Niobrara Formation, and the Coalmont Formation is adequately isolated. No offset mitigation required.</p> <p>Evaluated offset horizontal producing (PR) well Mutual #2-30H (057-06465), Sidetrack 01 wellbore TD at 10975' and completed in the Niobrara Formation. First String intermediate top of cement is 3170', with adequate isolation of the Niobrara production zone (top perforation at 7118' and First String shoe at 7090'). The First String cement coverage is lacking across the Coalmont Formation from 3170' to the surface casing shoe at 931'. A production liner is cemented across the Niobrara completion and up into the First String. Offset mitigation not required because of the wellbore orientation and lateral separation between wellbores (approximately 1,290' toe-to-toe for the proposed Castle 0780 1-17H20 well and this existing well). Mutual #2-30H is not within 1,500' of any other proposed wells on the pad, other than the Castle 0780 1-17H20 well.</p> <p>Evaluated offset permitted (XX) well Mutual #03-19H (057-06470), which has not been drilled (confirmed by COGCC Field Inspection Report #200290286, dated 11/18/2010), and the well's Form 2 Application for Permit to Drill #1990947, expired on 6/17/2009. The design of this well would not meet current standards, which require full isolation of the Coalmont Formation. Any refile of a Permit to Drill for the Mutual #03-19H well would require full isolation of the Coalmont Formation. No offset mitigation required because this well has an expired Permit to Drill, and the well was not drilled.</p> <p>Evaluated offset horizontal PR well Hebron #1-18H (057-06501), TD at 9994' and completed in the Niobrara Formation. First String cement coverage appears to extend above the surface casing shoe (set at 1054'), with adequate isolation of the Coalmont Formation and the Niobrara production zone (top perforation at 7441'). No offset mitigation required.</p> <p>Evaluated offset horizontal PR well Hebron #5-18H (057-06502), TD at 11408' and completed in the Niobrara Formation. First String cement coverage appears to extend above the surface casing shoe (set at 1028'), with adequate isolation of the Coalmont Formation and the Niobrara production zone (top perforation at 7161'). No offset mitigation required.</p> <p>Evaluated offset XX well Mutual #01-17H (057-06534) Form 2 Application for Permit to Drill # 400591335. The design of this well meets standards; no offset mitigation required.</p> <p>Evaluated offset XX well Hebron #01-18HR (057-06536) Form 2 Application for Permit to Drill # 400596809. The design of this well meets standards; no offset mitigation required.</p>		
Engineer	Operator provided an anti-collision report, attached to this form as "Other." Offset well(s) within 150' of this wellbore are operated by SandRidge as of 1/8/2016 (the same operator as this proposed well). Therefore, neither offset operator notice nor anti-collision BMPs are required by rule. Removed anti-collision BMP per operator agent request. Removed Stimulation Setback Consent Letter #400960949 per operator agent request.	1/8/2016 10:26:11 AM	
Engineer	The Coalmont Formation is considered a potential freshwater resource in the North Park Basin (CGS Ground Water Atlas of Colorado, 2003). The proposed surface casing setting depth of 2500' may or may not cover the entire formation. Minimum cement isolation standards are specified in Condition of Approval #2.	1/5/2016 5:11:51 PM	
Engineer	Offset water well check: COGCC evaluated offset water wells within one mile of this proposed well's surface hole location. This information was used in addition to locally-available geophysical logs and hydrogeologic information to evaluate the adequacy of the operator's proposed surface casing setting depth. The deepest water well within one mile is 101 feet.	1/5/2016 5:09:36 PM	
Permit	Passed completeness.	12/30/2015 11:24:34 AM	

Permit	Returned to draft. Section # for top of Niobrara incorrect on well location tab.	12/29/2015 3:11:15 PM
Total: 11 comment(s)		
<div></div>		