

Noble Energy, INC
Gill Land Assoc. 22-04
05-123-11360

Current Wellbore Schematic

Re-enter and re-plug

KB elev - 4897'

GL elev - 4886'

Weld cap on 8.625" sur csg

10sxs cement plug at surface

8.625" surf csg set @ 220'
200sxs cement to surface

Balanced Cement Plug: 180'/300'
70sxs 50/50 POZ cmt with 2% gel

Deepest Water well: 280'

Base Fox Hills 419'

Balanced Cement Plug: 3450'/3550'
65sxs 50/50 POZ cmt with 2% gel

7.865" Open Hole to 6450'

4.500" 11.6#/ft Prod Csg
6450'/7026'
200sxs cmt

10' cement on top
CIBP 6860'

TD = 7040'

Hunter Dunham
2/4/2016