

Noble Energy, INC  
Gill Land Assoc. 22-04  
05-123-11360

### Current Wellbore Schematic

Re-enter and re-plug  
KB elev - 4897'  
GL elev - 4886'

Weld cap on 8.625" sur csg

10sxs cement plug at surface

8.625" sur csg set @ 220'  
200sxs cement to surface

Cement Plug: 0'/550'  
200sxs cmt

Deepest Water well: 280'

Base Fox Hills 419'

Balanced Cement Plug: 3450'/3550'  
65sxs 50/50 POZ cmt with 2% gel

7.865" Open Hole to 6450'

4.500" 11.6#/ft Prod Csg  
6450'/7026'  
200sxs cmt

10' cement on top  
CIBP 6860'

TD = 7040'

Hunter Dunham  
2/4/2016